



## REPORT ON NEGATIVE ENCLOSURE TESTING

Atlanta Facility  
Indoor Air System (IA-1)

Sterigenics US, LLC  
2015 Spring Road, Suite 650  
Oak Brook, IL 60523  
Client Reference No. 172076.000.OJ

CleanAir Project No. 14004-1  
A2LA ISO 17025 Certificate No. 4342.01  
A2LA / STAC Certificate No. 4342.02  
Revision 0, Final Report  
May 27, 2020

## COMMITMENT TO QUALITY

To the best of our knowledge, the data presented in this report are accurate, complete, error free and representative of the actual emissions during the test program. Clean Air Engineering operates in conformance with the requirements of ASTM D7036-04 Standard Practice for Competence of Air Emission Testing Bodies.

*Report Writer:*



May 27, 2020

Kenny Sullivan  
Project Manager  
ksullivan@cleanair.com  
(800) 627-0033 ext. 4527

Date

I hereby certify that the information contained within the final test report has been reviewed and, to the best of my ability, verified as accurate.

*Independent Report and Appendix Reviewer:*



May 27, 2020

Bill Ansell, QSTI  
Midwest Engineering Group Technical Leader  
bansell@cleanair.com  
(800) 627-0033 ext. 4545

Date

---

## REPORT REVISION HISTORY

---

<b>Version</b>	<b>Revision</b>	<b>Date</b>	<b>Pages</b>	<b>Comments</b>
Draft	D0a	04/15/20	All	Draft version of original document.
Final	0	05/27/20	All	Final version of original document.

---

## PROJECT PERSONNEL

---

<b>Name</b>	<b>Affiliation</b>	<b>Project Responsibility</b>
Kevin Wagner	Sterigenics US, LLC	Client Contact
Dave De Fina	Sterigenics US, LLC	Client Contact
Steve Farnsworth	Sterigenics US, LLC	Plant Contact
Joshua Pittman	Georgia Department of Natural Resources, Environmental Protection Division	State Representative
Ray Shen	Georgia Department of Natural Resources, Environmental Protection Division	State Representative
Davina Marraccini	Environmental Protection Agency (EPA) Region IV	Federal Representative
Kenny Sullivan	CleanAir	Project Manager / Field Leader / Report Writer
Josh Myers	CleanAir	Reporting Assistant
Bill Ansell	CleanAir	Independent Reviewer of Report
Nadia Lazzar	CleanAir	Report Coordinator

---

## TABLE OF CONTENTS

1. Project Overview .....	1
Test Program Summary .....	1
Test Program Details .....	1
Parameters .....	1
Schedule .....	2
Discussion .....	2
2. Results .....	3
3. Description of Installation .....	6
Process Description .....	6
Negative Enclosure Description.....	7
General .....	7
IA-1 System.....	8
NE Zones.....	13
4. Methodology .....	20
Procedures and Regulations.....	20
Methodology Discussion .....	20
NDO Identification / NE Dimensional Measurements / NEAR .....	20
Directional Flow.....	20
Differential Pressure.....	20
5. Appendix.....	22
Appendix A: Test Equipment Specifications and Calibrations.....	A
Appendix B: NE Evaluation Data Sheets .....	B
Appendix C: NDO Log and Sketches .....	C
Appendix D: NE Area Wall Sketches .....	D
Appendix E: CleanAir Resumes and Certifications .....	E

## LIST OF TABLES

Table 1-1: Summary of Results.....	1
Table 1-2: Test Schedule.....	2
Table 2-1: IA-1 – Capture Efficiency Criteria Evaluation.....	3
Table 2-2: IA-1 – NDO Identification .....	3
Table 2-3: IA-1 – NEAR Calculation.....	4
Table 2-4: IA-1 – NDO Directional Flow.....	4
Table 2-5: IA-1 – Pressure Differential .....	5
Table 3-1: IA-1 – System Features Index .....	12
Table 3-2: Zone A – System Features Index .....	15
Table 3-3: Zone B – System Features Index.....	16
Table 3-4: Zone C – System Features Index.....	19

## LIST OF FIGURES

Figure 3-1: Process Schematic.....	7
Figure 3-2: Facility NE Layout and Pressure Plan .....	8
Figure 3-3: IA-1 – Zone A Schematic.....	9
Figure 3-4: IA-1 – Zone B Schematic.....	10
Figure 3-5: IA-1 – Zone C Schematic.....	11
Figure 3-6: Zone A – Floor Plan .....	14
Figure 3-7: Zone B – Floor Plan.....	16
Figure 3-8: Zone C – Floor Plan.....	18

## ACRONYMS & ABBREVIATIONS

AAS (atomic absorption spectrometry)  
 acfm (actual cubic feet per minute)  
 ACI (activated carbon injection)  
 ADL (above detection limit)  
 AIG (ammonia injection grid)  
 APC (air pollution control)  
 AQCS (air quality control system(s))  
 ASME (American Society of Mechanical Engineers)  
 ASTM (American Society for Testing and Materials)  
 BDL (below detection limit)  
 Btu (British thermal units)  
 CAM (compliance assurance monitoring)  
 CARB (California Air Resources Board)  
 CCM (Controlled Condensation Method)  
 CE (capture efficiency)  
 °C (degrees Celsius)  
 CEMS (continuous emissions monitoring system(s))  
 CFB (circulating fluidized bed)  
 CFR (Code of Federal Regulations)  
 cm (centimeter(s))  
 COMS (continuous opacity monitoring system(s))  
 CT (combustion turbine)  
 CTI (Cooling Technology Institute)  
 CTM (Conditional Test Method)  
 CVAAS (cold vapor atomic absorption spectroscopy)  
 CVAFS (cold vapor atomic fluorescence spectrometry)  
 DI H<sub>2</sub>O (de-ionized water)  
 %dv (percent, dry volume)  
 DLL (detection level limited)  
 DE (destruction efficiency)  
 DCI (dry carbon injection)  
 DGM (dry gas meter)  
 dscf (dry standard cubic feet)  
 dscfm (dry standard cubic feet per minute)  
 dscm (dry standard cubic meter)  
 ESP (electrostatic precipitator)  
 FAMS (flue gas adsorbent mercury speciation)  
 °F (degrees Fahrenheit)  
 FB (field blank)  
 FCC (fluidized catalytic cracking)  
 FCCU (fluidized catalytic cracking unit)  
 FEGT (furnace exit gas temperatures)  
 FF (fabric filter)  
 FGD (flue gas desulfurization)  
 FIA (flame ionization analyzer)  
 FID (flame ionization detector)  
 FPD (flame photometric detection)  
 FRB (field reagent blank)  
 FSTM (flue gas sorbent total mercury)  
 ft (feet or foot)

ft<sup>2</sup> (square feet)  
 ft<sup>3</sup> (cubic feet)  
 ft/sec (feet per second)  
 FTIR (Fourier Transform Infrared Spectroscopy)  
 FTRB (field train reagent blank)  
 g (gram(s))  
 GC (gas chromatography)  
 GFAAS (graphite furnace atomic absorption spectroscopy)  
 GFC (gas filter correlation)  
 gr/dscf (grains per dry standard cubic feet)  
 > (greater than)/ ≥ (greater than or equal to)  
 g/s (grams per second)  
 H<sub>2</sub>O (water)  
 HAP(s) (hazardous air pollutant(s))  
 HI (heat input)  
 hr (hour(s))  
 HR GC/MS (high-resolution gas chromatography and mass spectrometry)  
 HRVOC (highly reactive volatile organic compounds)  
 HSRG(s) (heat recovery steam generator(s))  
 HVT (high velocity thermocouple)  
 IC (ion chromatography)  
 IC/PCR (ion chromatography with post column reactor)  
 ICP/MS (inductively coupled argon plasma mass spectrometry)  
 ID (induced draft)  
 in. (inch(es))  
 in. H<sub>2</sub>O (inches water)  
 in. Hg (inches mercury)  
 IPA (isopropyl alcohol)  
 ISE (ion-specific electrode)  
 kg (kilogram(s))  
 kg/hr (kilogram(s) per hour)  
 < (less than)/ ≤ (less than or equal to)  
 L (liter(s))  
 lb (pound(s))  
 lb/hr (pound per hour)  
 lb/MMBtu (pound per million British thermal units)  
 lb/TBtu (pound per trillion British thermal units)  
 lb/lb-mole (pound per pound mole)  
 LR GC/MS (low-resolution gas chromatography and mass spectrometry)  
 m (meter)  
 m<sup>3</sup> (cubic meter)  
 MACT (maximum achievable control technology)  
 MASS<sup>®</sup> (Multi-Point Automated Sampling System)  
 MATS (Mercury and Air Toxics Standards)  
 MDL (method detection limit)  
 µg (microgram(s))  
 min. (minute(s))  
 mg (milligram(s))

ml (milliliter(s))  
 MMBtu (million British thermal units)  
 MW (megawatt(s))  
 NCASI (National Council for Air and Stream Improvement)  
 ND (non-detect)  
 NDIR (non-dispersive infrared)  
 NDO (natural draft opening)  
 NESHAP (National Emission Standards for Hazardous Air Pollutants)  
 ng (nanogram(s))  
 Nm<sup>3</sup> (Normal cubic meter)  
 % (percent)  
 PEMS (predictive emissions monitoring systems)  
 PFGC (pneumatic focusing gas chromatography)  
 pg (picogram(s))  
 PJFF (pulse jet fabric filter)  
 ppb (parts per billion)  
 PPE (personal protective equipment)  
 ppm (parts per million)  
 ppm<sub>dv</sub> (parts per million, dry volume)  
 ppm<sub>wv</sub> (parts per million, wet volume)  
 PSD (particle size distribution)  
 psi (pound(s) per square inch)  
 PTE (permanent total enclosure)  
 PTFE (polytetrafluoroethylene)  
 QA/QC (quality assurance/quality control)  
 QI (qualified individual)  
 QSTI (qualified source testing individual)  
 QSTO (qualified source testing observer)  
 RA (relative accuracy)  
 RATA (relative accuracy test audit)  
 RB (reagent blank)  
 RE (removal or reduction efficiency)  
 RM (reference method)  
 scf (standard cubic feet)  
 scfm (standard cubic feet per minute)  
 SCR (selective catalytic reduction)  
 SDA (spray dryer absorber)  
 SNCR (selective non-catalytic reduction)  
 STD (standard)  
 STMS (sorbent trap monitoring system)  
 TBtu (trillion British thermal units)  
 TEOM (Tapered Element Oscillating Microbalance)  
 TEQ (toxic equivalency quotient)  
 ton/hr (ton per hour)  
 ton/yr (ton per year)  
 TSS (third stage separator)  
 USEPA or EPA (United States Environmental Protection Agency)  
 UVA (ultraviolet absorption)  
 WFGD (wet flue gas desulfurization)  
 %wv (percent, wet volume)

# 1. PROJECT OVERVIEW

## TEST PROGRAM SUMMARY

Sterigenics US, LLC (Sterigenics) contracted CleanAir Engineering (CleanAir) to complete negative enclosure (NE) verification testing on the Indoor Air System (IA-1) at the facility, located in Atlanta, Georgia.

The main objective of this test program was to perform verification testing to demonstrate that IA-1 meets 100% ethylene oxide (EtO) capture as requested in a Georgia Department of Natural Resources (DNR) Environmental Protection Division (EPD) letter to Sterigenics, dated October 9, 2019, entitled "Re: Request for additional information regarding Application No. 27153 received July 31, 2019 Sterigenics U.S., LLC, Atlanta, AIRS No: 06700093." The letter requested that Sterigenics conduct testing and engineering analyses to evaluate the modifications proposed in Application No. 27153. The modifications included the construction and implementation of a facility indoor air system that captures all fugitive emissions, removes emissions via a dry bed adsorption (DBA) system, and then exhausts effluent gas via a dedicated stack.

A summary of the test program results is presented below. Section 2 Results provides a more detailed account of the test conditions and data analysis.

**Table 1-1:  
 Summary of Results**

<u>Source</u> Constituent	Result	Standard <sup>1</sup>
<u>Indoor Air Control System</u> EtO Capture efficiency (%)	100	100

<sup>1</sup> Standard requested in Georgia DNR EPD letter to Sterigenics dated October 9, 2019 entitled "Re: Request for additional information regarding Application No. 27153 received July 31, 2019 Sterigenics U.S., LLC, Atlanta, AIRS No: 06700093".

## TEST PROGRAM DETAILS

### PARAMETERS

The test program included the following measurements:

- EtO capture efficiency, in percent (%);
- Identification and area determination of each natural draft opening (NDO);
- Ratio of total NDO area to total NE surface area;
- direction of air flow through all NDOs;
- Pressure differential between the interior and exterior of NE affected areas in inches of water (in. H<sub>2</sub>O).

## SCHEDULE

Testing was performed on March 24, 2020. The on-site schedule followed during the test program is outlined in Table 1-2.

**Table 1-2:  
 Test Schedule**

Location	Parameter	Date	Start Time	End Time
IA-1	NDO Identification, NE Dimensional Measurements	03/24/20	08:00	12:00
IA-1	NDO Direction Flow	03/24/20	13:00	14:00
IA-1	NE Pressure Differential	03/24/20	14:35	15:37

## DISCUSSION

### *Ethylene Oxide Capture Efficiency Determination*

Since 40 CFR 63.7, Subpart O does not specify the means of demonstrating 100% capture efficiency, CleanAir evaluated the enclosure surrounding the affected facility against a set of criteria ensuring 100% capture. The criteria for NE verification included the following:

1. the total area of all NDOs shall not exceed 5% of the total NE surface area;
2. the direction of air flow through all NDOs shall be into the enclosure;
3. All areas contained by the NE shall be under negative pressure;
4. All access doors and windows where areas are not included as NDOs and are not included in the calculations are closed during routine operation of the process;
5. All EtO emissions must be captured and contained for discharge through a control device.

An NDO enclosure area ratio (NEAR) was calculated to determine compliance with the first criteria. The NEAR was below the allowable limit of 5%. The direction of flow through each NDO during testing was into the NE. Each area in the NE was under negative pressure during testing. NE access points not considered NDOs were closed during testing, and all airflow in the indoor air system is captured and discharged through control devices. These were all verified on-site.

NDO identification and descriptions are presented in Table 2-2 on the following page. A detailed NE description, including floor and ceiling schematics, is discussed in Section 3 of this report. The NE was split into three areas designated Zone A, Zone B, and Zone C. Detailed sketches of NDOs and NE walls are included in Appendices C and D, respectively, of this report. Directional flow and pressure differential testing methodology is discussed in Section 4 of this report.



## 2. RESULTS

This section summarizes the test program results. Additional results are available in the report appendices.

**Table 2-1:  
 IA-1 – Capture Efficiency Criteria Evaluation**

NE VERIFICATION CRITERIA	Value / Observation During Test	Acceptable? (yes, no, or n/a)
1. The total area of all NDO's shall not exceed 5 percent of the surface area of the enclosures four walls, floor and ceiling.	0.031%	YES
2. The direction of air flow through all NDO's shall be into the enclosure.	IN	YES
3. The pressure differential across the enclosure shall be negative.	≈ -0.0295"H <sub>2</sub> O	YES
4. All access doors and windows that were not included as NDO's above shall remain closed during source operation. <sup>1</sup>	Verified	YES
5. All EtO must be captured and contained for discharge through a control device. <sup>1</sup>	Verified	YES

If all of the above criteria are met, then an enclosure is considered to be a negative enclosure and the EtO capture efficiency can be assumed to be 100%.

**Table 2-2:  
 IA-1 – NDO Identification**

NDO	Description	Dimensions (W x H)	Area (ft <sup>2</sup> )
<b>Zone A</b>			
A-1	Mandoor Louver near Chamber #7	22" x 22"	3.36
A-2	Ceiling Louver in SE Corner	4' x 4'	16.0
<b>Zone B</b>			
B-1	Ceilcote Scrubber Room Drainage Outlet	35" x 1"	0.24
B-2	Ceilcote Scrubber Room East Wall Louver	4' x 4'	16.0
<b>Zone C</b>			
C-1	Shipping Dock 16 with Truck (gaps around seals)	2 @ 1" x 10', 1 @ 4.5" x 9'	5.05
C-2	Shipping Dock 17 with Truck (gaps around seals)	2 @ 1" x 10', 1 @ 4.5" x 9'	5.05
<b>Total NDO Area</b>			
A <sub>NDO</sub>	Total area of NDOs (ft <sup>2</sup> )		<b>45.70</b>

**Table 2-3:  
 IA-1 – NEAR Calculation**

NE Area	Surface Area (SA) (ft <sup>2</sup> )	Description
<b>Zone A</b>		
Floor	14,120	Chamber Room floor
Ceiling	14,120	Chamber Room ceiling, contains NDO A-2
North Wall	2,088	Chamber Room North wall, contains NDO A-1, multiple mandoor
South Wall	2,088	Chamber Room South wall, EtO storage door
East Wall	3,714	Chamber Room East wall, receiving speed door, door to transfer corridor
West Wall	3,918	Chamber Room West wall, 1 mandoor, garage door for chamber transfer
<b>Zone B</b>		
Floor	11,561	Transfer corridor floor, Ceilcote Scrubber Room floor
Ceiling	11,561	Transfer corridor ceiling, Ceilcote Scrubber Room ceiling
North Wall	4,464	Preconditioning room wall, receiving wall
South Wall	4,728	Transfer corridor wall, Ceilcote Scrubber Room South Wall, contains NDO B-1
East Wall	1,056	Ceilcote Scrubber Room East wall, contains NDO B-2
West Wall	1,296	Preconditioning East wall, transfer corridor wall excluded
<b>Zone C</b>		
Floor	25,090	Shipping area floor, Aeration Room floor, AAT Scrubber Room floor
Ceiling	25,090	Shipping area ceiling, Aeration Room ceiling, AAT Scrubber Room ceiling
North Wall	4,448	Shipping area North wall, contains NDO C-1 & C-2, AAT Scrubber Room North wall
South Wall	4,652	Shipping area South wall, Aeration Room South wall
East Wall	5,908	Shipping area East wall, Aeration Room East wall
West Wall	5,440	Shipping area West wall, AAT Scrubber Room West wall
<b>NE Total</b>	<b>145,342</b>	
NE Total Area	145,342	
NDO Total Area	45.70	
NE Total Surface Area <sup>1</sup>	145,296	
<b>NEAR</b>	<b>0.031%</b>	<i>Limit = &lt; 5%</i>

<sup>1</sup> NE total area minus NDO total area

**Table 2-4:  
 IA-1 – NDO Directional Flow**

NDO ID	Directional Flow					
	<u>1</u>	<u>2</u>	<u>3</u>	<u>4</u>	<u>5</u>	<u>6</u>
A-1	IN	IN	IN	IN	IN	IN
A-2	IN	IN	IN	IN	IN	IN
B-1	IN	IN	IN	IN	IN	IN
B-2	IN	IN	IN	IN	IN	IN
C-1	IN	IN	IN	IN	IN	IN
C-2	IN	IN	IN	IN	IN	IN
Start: 13:00	Total # of Trials:					36
Stop: 14:00	Total Number of 'IN':					36
	% 'IN':					100%

**Table 2-5:  
 IA-1 – Pressure Differential**

NE Area	Zone A		Zone B - TC <sup>1</sup>		Zone B - CS <sup>2</sup>	
	Time	Pressure Drop	Time	Pressure Drop	Time	Pressure Drop
<u>Run</u>	<u>(hh:mm)</u>	<u>(in H<sub>2</sub>O)</u>	<u>(hh:mm)</u>	<u>(in H<sub>2</sub>O)</u>	<u>(hh:mm)</u>	<u>(in H<sub>2</sub>O)</u>
1	14:20	-0.0390	14:35	-0.0211	14:50	-0.0078
2	14:23	-0.0540	14:38	-0.0274	14:53	-0.0173
3	14:26	-0.0451	14:41	-0.0298	14:56	-0.0195
4	14:29	-0.0427	14:44	-0.0360	14:59	-0.0200
5	14:32	-0.0493	14:47	-0.0278	15:02	-0.0076
	<b>Average</b>	<b>-0.0460</b>	<b>Average</b>	<b>-0.0284</b>	<b>Average</b>	<b>-0.0145</b>
	<b>Maximum</b>	<b>-0.0540</b>	<b>Maximum</b>	<b>-0.0360</b>	<b>Maximum</b>	<b>-0.0200</b>
	<b>Minimum</b>	<b>-0.0390</b>	<b>Minimum</b>	<b>-0.0211</b>	<b>Minimum</b>	<b>-0.0076</b>

NE Area	Zone C - AR/SA <sup>3</sup>		Zone C - AAT <sup>4</sup>		NE (Overall)	
	Time	Pressure Drop	Time	Pressure Drop	Time	Pressure Drop
<u>Run</u>	<u>(hh:mm)</u>	<u>(in H<sub>2</sub>O)</u>	<u>(hh:mm)</u>	<u>(in H<sub>2</sub>O)</u>	<u>(hh:mm)</u>	<u>(in H<sub>2</sub>O)</u>
1	15:07	-0.0102	15:25	-0.0459	N/A	↓
2	15:10	-0.0178	15:28	-0.0607		
3	15:13	-0.0125	15:31	-0.0442		
4	15:16	-0.0048	15:34	-0.0484		
5	15:19	-0.0086	15:37	-0.0398		
	<b>Average</b>	<b>-0.0108</b>	<b>Average</b>	<b>-0.0478</b>	<b>Average</b>	<b>-0.0295</b>
	<b>Maximum</b>	<b>-0.0178</b>	<b>Maximum</b>	<b>-0.0607</b>	<b>Maximum</b>	<b>-0.0607</b>
	<b>Minimum</b>	<b>-0.0048</b>	<b>Minimum</b>	<b>-0.0398</b>	<b>Minimum</b>	<b>-0.0048</b>

**Limit: ≥ 0.0000**

<sup>1</sup>Transfer corridor

<sup>2</sup>Ceilcote Scrubber Room

<sup>3</sup>Aeration room / Shipping area

<sup>4</sup>AAT Scrubber Room

*End of Section*

### 3. DESCRIPTION OF INSTALLATION

#### PROCESS DESCRIPTION

---

Sterigenics US, LLC operates a commercial contract sterilization facility in Atlanta, Georgia, which utilizes EtO to sterilize its customers' product. It also has the ability to use propylene oxide to treat nutmeats.

When EtO is used for medical device sterilization, the medical devices must have a specifically-defined sterilization process, which is validated for a specific sterilization chamber or chambers. The Atlanta facility uses 10 sterilization chambers ranging in size from five pallets to up to 30 pallets. While all 10 sterilization chambers are similar in design, each chamber may only process products approved for that chamber and cannot process other products that have not been validated and approved by the appropriate regulatory agency for that specific chamber.


The sterilization process begins with evacuating the air from the chamber and introducing nitrogen (N<sub>2</sub>). While under negative pressure inside the chamber, EtO is introduced into the sterilization chamber to sterilize the product. Once EtO is introduced, the dwell stage can last from 30 minutes to up to several hours, according to the validated cycle for the product. Once complete, the sterilization chamber vacuum pumps remove most of the EtO from the chamber by exhausting and purging with N<sub>2</sub> multiple times. Vacuum pump emissions are routed to the ceilcote wet acid scrubber, which is then routed to the existing Advanced Air Technologies (AAT) wet acid scrubber with dry bed reactor, then to additional polishing beds, and finally to a common stack.

Once the sterilization chamber process is complete and the chamber door is partially opened, the backvent fan activates to extract residual amounts of EtO from the chamber. This fan remains on while the chamber door is open. After 15 minutes, the pallets of product are removed from the sterilization chamber and placed into aeration rooms to further off-gas residual EtO. Both the backvents and aeration rooms are ducted to the AAT and treated with dry bed reactors, and then to a common stack.

A negative pressure system has been installed to capture air internally from chamber rooms, work aisles, processed product storage, and shipping areas. This captured air is ducted to a new dry bed control system consisting of 18 dry beds and then to a dedicated stack.

The testing reported in this document was performed on the facility negative pressure (NP) system. Testing was performed in areas deemed part of the negative pressure area. A schematic of the process is shown in Figure 3-1 on the following page.

**Figure 3-1:  
 Process Schematic**



## NEGATIVE ENCLOSURE DESCRIPTION

### GENERAL


The NE consists of three zones: Zone A, Zone B, and Zone C. Zone A includes the chamber room area. Zone B includes the ceilcote scrubber room and the corridor abutting the pre-conditioning room where sterilized pallets are transferred via forklift from the chamber room to the aeration room. For the purposes of this report, this is referred to as the work aisle or transfer corridor. Zone C includes the shipping area, aeration room, and AAT scrubber enclosure. The receiving area and pre-conditioning room are not included in the NE.

Six NDOs were identified during testing: A-1, A-2, B-1, B-2, C-1, and C-2. Locations, dimensions, descriptions, and areas are listed in Table 3-1.

Access in and out of the NE to/from non-NE areas include several manddoors and garage speed doors. All manddoors and garage speed doors remain closed during normal operations. Garage speed doors are movement-activated, allowing them to automatically open and close. These doors provide passthrough for forklifts and product for only seconds at a time. The NE contains many mothballed louvers and vents that are either capped or disconnected from the indoor air system. Each cap and disconnection were verified on-site.

A general NE layout, with NE area and negative pressure design overlay, is presented in Figure 3-2.

**Figure 3-2:  
 Facility NE Layout and Pressure Plan**




### IA-1 SYSTEM

The IA-1 system consists of a network of ducts that are routed to a bank of dry beds, then exhausted out of a dedicated stack. The dry beds are located in the receiving area outside of the NE. Flow is induced through the system via a blower on the roof. The blower is controlled by an Allen-Bradley Panelview Plus 1250 operator interface and is rated for approximately 18,000 cfm. All indoor air in the NE is routed to a control device: air from the aeration room and south end of the shipping area is routed to the AAT scrubber, air from back vents during transfer and chamber room outlet ducts during non-transfer periods are routed to the AAT scrubber, and air from all other areas in the NE are routed to the DBA system. Air flow in the system is controlled by a series of dampers that can dictate the quantity of air being induced from each zone. When proportionately more air is being drawn from a specific zone, the configuration is labeled as "strategic air from Zone X." During directional flow and pressure differential testing, the configuration was strategic air from Zone B.

The IA-1 ductwork schematic is presented in Figures 3-3 through 3-5. The ductwork is highlighted in blue.

**Figure 3-3:  
IA-1 – Zone A Schematic**



**Figure 3-4:**  
**IA-1 – Zone B Schematic**







Figure 3-5:  
IA-1 – Zone C Schematic



A ductwork schematic features index is presented in Table 3-1.

**Table 3-1:  
 IA-1 – System Features Index**

<u>Feature</u>	<u>Description</u>	<u>Dimensions</u>
<b>Zone A - IA-1 System Feature Index</b>		
DMP-1	Damper 1. Located in Zone B corridor outside of boiler room. 16" diameter duct.	16" dia.
A-2	NDO. Ceiling louver.	4x4'
DMP-2	Damper 2. Duct draws air from chamber room area to dry bed scrubber	16" dia.
DMP-3	Damper 3. Duct draws air from chamber room area to dry bed scrubber	16" dia.
DMP-4	Damper 4. Duct draws air from chamber room area to dry bed scrubber	16" dia.
DMP-5	Damper 5. Duct draws air from chamber room area to dry bed scrubber	16" dia.
DMP-6	Damper 6. Duct draws air from chamber room area to dry bed scrubber	16" dia.
VNT-1	Ceiling vent 1. Open when BV closed. Closed when BV open. Ductwork goes to AAT scrubber.	14" dia.
VNT-2	Ceiling vent 2. Open when BV closed. Closed when BV open. Ductwork goes to AAT scrubber.	14" dia.
VNT-3	Ceiling vent 3. Open when BV closed. Closed when BV open. Ductwork goes to AAT scrubber.	14" dia.
VNT-4	Ceiling vent 4. Open when BV closed. Closed when BV open. Ductwork goes to AAT scrubber.	14" dia.
BV-1	Back vent: Chamber 1.	8" dia.
BV-2	Back vent: Chamber 2.	8" dia.
BV-3	Back vent: Chamber 3.	8" dia.
BV-4	Back vent: Chamber 4.	8" dia.
BV-5	Back vent: Chamber 5.	12" dia.
BV-6	Back vent: Chamber 6.	16" dia.
BV-7	Back vent: Chamber 7.	12" dia.
BV-8	Back vent: Chamber 8. Note: there is no chamber 9.	12" dia.
BV-10	Back vent: Chamber 10.	16" dia.
BV-11	Back vent: Chamber 11.	16" dia.
CAP-1	Chamber 1 unused vent cap.	8 x 1'
CAP-2	Chamber 2 unused vent cap.	8 x 1'
CAP-3	Chamber 3 unused vent cap.	8 x 1'
CAP-4	Chamber 4 unused vent cap.	8 x 1'
CAP-5	Chamber 5 unused vent cap.	6' x 8"
CAP-7	Chamber 7 unused vent cap.	12" dia.
CAP-11	Ceiling louver above chamber 11 remains shut/capped.	3 x 3'
DRY BED SCRUBBER	A bank of dry catalyst scrubber beds. Air is supplied from ceiling ductwork in Zones A, B and C and is exhausted to the stack.	--
STACK	Rooftop emission point downstream from dry bed scrubber.	--
<b>Zone B - IA-1 System Feature Index</b>		
DMP-1	Damper 1. Located in Zone B corridor outside of boiler room. 16" diameter duct.	16" dia.
DMP-7	Damper 7. Located in the Work Aisle. Controls strategic air. 6" diameter duct.	6" dia.
<b>Zone C - IA-1 System Feature Index</b>		
DMP-8	Damper 8. Duct draws air from processed shipping area to dry bed scrubber. 16" dia. duct.	16" dia.
DMP-9	Damper 9. Duct draws air from processed shipping area to dry bed scrubber. 16" dia. duct.	16" dia.
DMP-10	Damper 10. Duct draws air from shipping area to AAT scrubber. 16" dia. duct.	16" dia.
DMP-11	Damper 11. Duct draws air from AAT Scrubber Room to AAT-VNT. 6" dia. duct.	6" dia.
AAT-C1	Blower/fan in Aeration #1 area. Air is ducted to AAT Scrubber.	1.5 x 1.5'

## NE ZONES

### Zone A

Zone A includes the chamber room area. Two NDOs are located in Zone A; A-1 and A-2. Refer to Table 2-2 for Zone A NDO details.


The chamber room consists of 10 sterilization chambers equipped with back vents, two east garage speed doors, and several mandoor. When chamber doors are opened, back vents are activated and routed to the AAT scrubber. When chamber doors are closed, there are four outlet ducts that are activated and routed to the AAT scrubber. During directional flow and pressure differential testing, Chamber 10 door was open and Chamber 11 door was ajar. Unsterilized product is transferred via forklift from the pre-conditioning room to the chamber room through the northernmost east garage speed door. There is routine traffic through this door only during peak operation hours. The door opens and closes automatically. Sterilized product is transferred via forklift out of the chamber room through the southernmost east garage speed door. This door is used one to two times a day. The area of the shared wall between Zone A and Zone B is excluded in the NEAR calculation, since it is contained within the NE.

Periodically, delivered EtO drums are transferred from the receiving area through the chamber room to the drum storage area. The drums are transferred into the chamber room through a north mandoor and are then carted to the drum storage area on the south side of the chamber room through a mandoor backed up by strip curtains. During transfer, as an administrative facility rule, only one of the doors is allowed open at a time.

A 3' x 3' forced draft louver is located above the westernmost mandoor on the north side of the chamber room and draws about 4,725 cfm into the chamber room. An anemometer was utilized to approximate air velocity, in feet per minute (fpm), coming into the chamber room via the louver. The anemometer specifications are presented in Appendix A of this report.

A floor plan of Zone A is presented in Figure 3-6 on the following page. Zone A features index is presented in Table 3-2 on page 15.

**Figure 3-6:  
Zone A – Floor Plan**



**Table 3-2:  
 Zone A – System Features Index**

<u>Feature</u>	<u>Description</u>	<u>Dimensions</u>
<b>Zone A Floor Feature Index</b>		
A-1	NDO. Louver on the bottom of door	1.83 X 1.83'
A-2	NDO. Ceiling Louver.	4' x 4'
A-3	Garage door. Only opens to add/remove chambers.	16.5 x 16.25'
A-4	Mandoor. Normally closed.	3.5 x 6.83'
A-5	Former NDO. Capped.	3.5 x 3.5'
A-6	Former NDO. Capped.	3.5 x 3.5'
A-7	Mandoor. Normally closed.	3.5 x 6.83'
A-8	Garage speed door. Automatically closes.	10 x 10'
A-9	Mandoor. Normally closed.	3.5 x 10'
A-10	Garage speed door. Opens once per day. This is the same feature as B-10	10 x 7.5'
A-11	Mandoor. Normally closed.	3.5 x 6.83'
A-12	Garage door reduced to smaller strip curtain door (4'x7').	14 x 9.5'

*Zone B*


Zone B includes the ceilcote scrubber room and the work aisle. Two NDOs are located in Zone B: B-1 and B-2. Refer to Table 2-2 for Zone B NDO details. Both Zone B NDOs are located in the ceilcote scrubber room. NDO B-1 is the terminus of a water drainage outlet running along the west side of the ceilcote scrubber room. The outlet is an opening in the wall approximately 2' in width, 6" in height and is mainly covered by a plastic curtain. The NDO area is considered the gaps between the curtain and gutter.

Zone B includes several manddoors and several garage doors. All manddoors remain closed during normal operation. Sterilized product is transferred via forklift out of the chamber room through the west garage speed door. Four regular garage doors are located on the south side of the work aisle. One of the work aisle garage doors adjoins the boiler room, and the other three garage doors adjoin storage areas. A large garage speed door is located on the north side of the work aisle and adjoins the receiving area. The large garage speed door is used approximately once a day. An open pathway approximately 10' x 12' connects Zone B and Zone C. The area of the shared wall containing the open pathway is excluded in the NEAR calculation since it is contained within the NE.

The work aisle abuts the pre-conditioning room. The pre-conditioning room walls and ceiling do not entirely reach the ceiling of the NE. There is approximately 2.5' of headspace above the pre-conditioning room. This surface area is included in the NEAR calculation.

A floor plan of Zone B is presented in Figure 3-7 on the following page. Zone B features index is presented in Table 3-3 on the following page.

**Figure 3-7:  
 Zone B – Floor Plan**



**Table 3-3:  
 Zone B – System Features Index**

<u>Feature</u>	<u>Description</u>	<u>Dimensions</u>
<b>Zone B Floor Feature Index</b>		
B-1	NDO. Drainage opening.	
B-2	NDO. Wall louver.	4 x 4'
B-3	Mandoor.	3 x 7'
B-4	Mandoor.	3 x 6.83'
B-5	Garage door.	10 x 10'
B-6	Garage door.	10 x 10'
B-7	Garage door.	10 x 10'
B-8	Mandoor.	3 x 7'
B-9	Garage door. (10'W x 12'H)	10 x 12'
B-10	Speed door. Opens once per day. This is the same feature as A-10.	10 x 7.5'
B-11	Mandoor.	3 x 7'
B-12	Mandoor.	3 x 7'
B-13	Mandoor.	3 x 7'
B-14	Garage speed door. Rarely opened (10'W x 14'H).	10 x 14'
B-15	Open pathway to Zone C. Same feature as C-8.	10 x 12'
B-16	Mandoor.	3.5 x 7'

### Zone C

Zone C includes the shipping area, aeration room, and AAT scrubber enclosure. Two NDOs are located in Zone C: C-1 and C-2. Refer to Table 2-2 for Zone C NDO details. The areas of NDO C-1 and C-2 are considered the gaps between the shipping docks and dock seals, and stationed semi-trucks. The NDO areas are considered variable, depending on positioning of the semi-truck at the dock. Gaps were measured at both docks and area dimensions were averaged. For purposes of this report, the NDO areas for C-1 and C-2 are considered equal.

There are three docks in the shipping area. As a facility administrative rule, only two docks are allowed to receive a semi-truck at a time.


The shipping area abuts administrative offices. The administrative offices walls and ceiling do not entirely reach the ceiling of the NE. There is approximately 14' of headspace above the administrative offices. This surface area is included in the NEAR calculation. HVAC ducts from the top of the offices are routed directly above to the roof where it is exhausted. These ducts are isolated from the NE indoor air and are not part of IA-1.

There are no NDOs in the aeration room. The aeration room has two garage speed doors acting as access points for product to be delivered. There is a louver connecting the shipping area to the aeration room located above the north garage speed door. These doors automatically open and close. A centrally-located fan in the ceiling of the aeration room draws residual EtO-contaminated air to the AAT scrubber. The aeration room walls and ceiling do not entirely reach the ceiling of the NE. There is approximately 2' of headspace above the aeration room. This surface area is included in the NEAR calculation.

The AAT scrubber room is isolated from the shipping area. The access point to the scrubber room is a small manual garage door that abuts the receiving area and is closed during normal operation. There are no NDOs in the AAT scrubber room.

A floor plan of Zone C is presented in Figure 3-8 on the following page. Zone C features index is presented in Table 3-4 on page 19.

Figure 3-8:  
Zone C – Floor Plan





**Table 3-4:  
 Zone C – System Features Index**

<u>Feature</u>	<u>Description</u>	<u>Dimensions</u>
<b>Zone C Floor Feature Index</b>		
C-1	NDO. Shipping door. Dock 16.	9.25 X 10'
C-2	NDO. Shipping door. Dock 17.	9.25 X 10'
C-3	Alternate shipping door. Not an NDO. Dock 18.	9.25 X 10'
C-4	Mandoor.	3 x 7'
C-5	Garage door.	8 x 10'
C-6	4' high exit door.	3 x 7'
C-7	Garage door.	6 x 8'
C-8	Open pathway to Zone B. Same feature as B-15.	10 x 12'
C-9	Exit Mandoor.	3 x 7'
C-10	Mandoor.	3 x 7'
C-11	Speed garage door.	8 x 11'
C-12	Mandoor.	3 x 7'
C-13	Speed garage door 8 x 11'. Louver above door 6 x 2'.	8 x 11'
C-14	Mandoor.	3 x 7'
C-15	Mandoor.	3 x 7'
C-16	Mandoor.	3 x 7'
C-17	Mandoor.	3 x 7'
C-18	Old NDO. Sealed.	4 x 6'

*End of Section*

## 4. METHODOLOGY

### PROCEDURES AND REGULATIONS

---

The test program sampling measurements followed procedures and regulations outlined by the United States Environmental Protection Agency (USEPA) and the Georgia DNR EPD. Appendix A includes specifications of sampling apparatuses.

CleanAir follows specific QA/QC procedures outlined in the individual methods and in USEPA "Quality Assurance Handbook for Air Pollution Measurement Systems: Volume III Stationary Source-Specific Methods," EPA/600/R-94/038C. Additional QA/QC measures are outlined in CleanAir's internal Quality Manual.

### METHODOLOGY DISCUSSION

---

#### NDO IDENTIFICATION / NE DIMENSIONAL MEASUREMENTS / NEAR

NDOs were identified, logged, and measured during testing. An NDO is defined as any permanent opening in the NE that is not connected to a duct in which a fan is installed. Dimensions for all NE area walls, floors, and ceilings were measured during testing. Areas were calculated based on measurements collected on-site. An NEAR was calculated as the total area of NDO as a percentage of total NE surface area. The dimensions of the enclosure were measured with a tape measure, measuring wheel, and laser distance finder.

#### DIRECTIONAL FLOW

The direction of flow through each NDO was observed at 10-minute intervals for one hour. Direction of flow was verified using smoke tubes.

#### DIFFERENTIAL PRESSURE

Pressure drop across the NE was measured with a calibrated electronic micromanometer. The micromanometer was placed in a centralized location within an NE area and a length of Tygon tubing was ran to a location outside of the NE. Five pressure drop measurements were recorded in five NE areas: the chamber room, the work aisle, the ceilcote scrubber room, the shipping/aeration room areas, and the AAT scrubber room. Pressure drops were recorded over a period of 12 minutes in each NE area tested. Individual pressure drop measurements were not measured in the aeration room because the aeration room is contained by the shipping area and there was no NDO identified within the confines of the area.

The micromanometer used to measure pressure drop has a recommended maximum length of tubing specification of 18'. Tubing used to measure pressure drop during testing was greater than 18'. A bench study regarding the effect of length of tubing on the micromanometer used during testing was conducted by CleanAir post-mobilization. The results of the study are presented in Appendix A of this report. The study concluded that there is negligible statistical bias in readings for tubing up to 300'.

An approximate NE face velocity was calculated to further verify that the NE is under negative pressure. The calculated face velocity into the NE is approximately 286 fpm. The face velocity was calculated as the difference of the average stack volumetric flow observed on the Allen-Bradley Panelview Plus 1250 operator interface (17,800 cfm) and the volumetric flow calculated at the Zone A forced draft louver (4,725 cfm), divided by the total NDO area (45.70 ft). An anemometer was utilized to approximate air velocity, in fpm, coming into the chamber room via the louver. The anemometer specifications are presented in Appendix A of this report. This number is an estimate and should be considered with discretion. EPA promulgated methods were not used to calculate volumetric flow. Air pressure, temperature, and molecular weight of the volumetric flows measured were assumed to be approximately equal and near standard conditions.

---

*End of Section*

## 5. *APPENDIX*

Appendix A: Test Equipment Specifications and Calibrations

Appendix B: NE Evaluation Data Sheets

Appendix C: NDO Log and Sketches

Appendix D: NE Area Wall Sketches

Appendix E: CleanAir Resumes and Certifications

## APPENDIX A: TEST EQUIPMENT SPECIFICATIONS AND CALIBRATIONS

**This Page Intentionally Left Blank**

## Shortridge AirData Multimeter ADM-860C



### RENTAL AND APPLICATION NOTES:

- Shipping Weight: 21 lbs.
- Air velocity readings are displayed as local density, true air velocity or flow.
- Internal calibration, temperature compensation, range selection and zeroing are fully automatic with each reading. No external adjustments needed.
- Memory can hold up to 100 readings for individual recall and can give a reading total and average.
- The max. recommended length of pneumatic tubing for the measurement of airflow, velocity or differential pressure is 18 ft. Minimum is ID 3/16".

### SPECIFICATIONS:

- Weight: 32 oz.
- Dimensions: 6" x 6.4" x 2.7".
- Power: 120VAC, 60 Hz, 8w.
- Output: RS-232.
- Response Time: 1 sec. at high pressure inputs, 7sec. at inputs less than 0.003wc. Extremely low pressure/flow/velocity inputs require longer sample times.
- Air Velocity: 25-29,000 fpm w/ standard pitot tube, 25-5,000 fpm w/ AirFoil probe, 25-2,500 fpm w/ VelGrid.
- Air Bleed: Each pressure measurement requires a small volume of air to pass through the meter. The pressure source must be capable of supplying this volume without significant depletion to ensure accurate measurements.
- Absolute Pressure: 10 - 40 in Hg. Max. safe pressure is 60 psi. Accuracy:  $\pm 2\%$  of reading  $\pm 0.1$  in Hg from 14-40 in Hg.
- Differential Pressure: 0.0001-60.00wc. Max. safe pressure is 20 psid. Accuracy:  $\pm 2\%$  of reading  $\pm 0.001$ wc from 0.05-50wc.
- Operational Temperature: 40°F - 104°F.
- Connections: 1/4" OD slip-on for 3/16" ID soft tubing.

## The measured effect of the length of pneumatic tubing on differential pressure measurements

---

The Shortridge AirData Multimeter (ADM) operating manual states: “TUBING: The maximum recommended length of pneumatic tubing for the measurement of air flow, velocity, or differential pressure is 18 feet.”

Due to the logistics in taking either static pressure readings or velocity pressure readings the length of the pneumatic tubing varies and can possibly be up to 300 feet in length.

### *Experimental Set-up*

To measure the effects of the pneumatic tubing length the following controlled measurements were made using an EPA designed and certified wind tunnel.

100 measurements were made at each of the following lengths of tubing attached to the ADM:

- 15 feet,
- 30 feet,
- 50 feet,
- 100 feet
- 300 feet.

The measurements were made to represent the static pressure between two locations such as in and out of an enclosure or taking duct/stack static pressure. One hundred readings were taken with each line length. Conditions in the wind tunnel were set to represent a low static pressure. Setup included:

- the (+) line is connected to the pitot at one end and the Shortridge ADM (+) inlet
- the (-) line is open to atmosphere on the pitot and the Shortridge ADM (-)
- the face of the pitot is perpendicular to the flow
- static pressure measure in tunnel was -0.0390 measured with an inclined manometer

### *Results*

Results showed relatively small differences in static reading – differences are in the third decimal place. Using the 15-foot as the standard, the differences between 15 and 30, 50 and 100 are virtually identical and very close to zero. The 300-foot length of tubing does show a slight negative bias in the average static reading compared to the 15-foot length – again these differences are in the third decimal place – about 0.0015. Note that this negative bias represents a worst-case scenario because it would possibly result in a smaller differential pressure drop than expected from a shorter length of tubing.

The ADM specification for accuracy is...“Accuracy is  $\pm 0.001$  in wc from 0.0500 to 50.00 in wc.” However, this controlled testing showed a real-world accuracy (precision) of approximately 0.004 in wc ( $2 \times \text{STDEV}$ ). Since the 0.0015 bias in the 300-foot line is less than the measurement precision of 0.0040, the bias is not significant.

Therefore, these data demonstrate that a tubing length up to 300 feet has a negligible effect on the differential pressure reading.

Figure 1-1 presents a summary of the data for the static pressure reading and Figure 1-2 shows a graphical representation of the statistical analysis.



**Figure 1-1:  
Summary of Static Readings**

Steady-flow conditions in wind tunnel set at 5.00Hz. All measurements taken between 1100 and 1230, 5 April 2020, by Jason Fugiel and Josh Myers

Static pressure: -0.039 inH2O  
 Temperature: 67.9 F  
 Atmospheric: 29.13 inHg  
 Approx Velocity: 8.5 ft/s  
 RH: 27 %

Differential Pressures in inH2O (abs. value). + only is out of flow, and is reading static pressure.


15ft      30ft      50ft      100ft      300ft  
 Static    Static    Static    Static    Static

	15ft	30ft	50ft	100ft	300ft
	Static	Static	Static	Static	Static
<b>Sum</b>	3.9187	3.9122	3.9116	3.9074	3.8582
<b>Average</b>	0.0392	0.0391	0.0391	0.0391	0.0386
<b>High</b>	0.0409	0.0405	0.0406	0.0425	0.0449
<b>Low</b>	0.0370	0.0373	0.0376	0.0370	0.0362
<b>Sum Sqrt.</b>	19.7947	19.7782	19.7772	19.7663	19.6407
<b>Average S</b>	0.1979	0.1978	0.1978	0.1977	0.1964
<b>High Sqrt.</b>	0.2022	0.2012	0.2015	0.2062	0.2119
<b>Low Sqrt.</b>	0.1924	0.1931	0.1939	0.1924	0.1903

**Figure 1-2:  
Data Statistical Analysis**

1. The differences between results from the 15-foot tubing length and each of the other lengths were found.
2. An Analysis of Variance (ANOVA) was performed for each set of differences. This is shown in the Figure.
3. The height of each green diamond shows the 95% confidence interval for the average of each set of differences.
4. The red line is zero difference. The blue line is the approximate real-world precision of the Shortridge instrument as measured by this study.
5. For the 30-foot, 50-foot, and 100-foot tubing lengths, the results are indistinguishable from the 15-foot length.
6. For the 300-foot length, the difference is measurable but is less than the precision of the instrument. Therefore, the difference is not significant.

**Oneway Analysis of SQRT Data By Label 2**



**Oneway Anova**

**Summary of Fit**

Rsquare	0.039336
Adj Rsquare	0.032059
Root Mean Square Error	0.002874
Mean of Response	0.000541
Observations (or Sum Wgts)	400

**Analysis of Variance**

Source	DF	Sum of Squares	Mean Square	F Ratio	Prob > F
Label 2	3	0.00013390	0.000045	5.4050	0.0012*
Error	396	0.00327018	8.258e-6		
C. Total	399	0.00340408			

**Means for Oneway Anova**

Level	Number	Mean	Std Error	Lower 95%	Upper 95%
15-30	100	0.000165	0.00029	-0.0004	0.00073
15-50	100	0.000176	0.00029	-0.0004	0.00074
15-100	100	0.000284	0.00029	-0.0003	0.00085
15-300	100	0.001540	0.00029	0.00098	0.00211

Std Error uses a pooled estimate of error variance



# AIRDATA MULTIMETER CERTIFICATE OF RECALIBRATION

Customer ID: 007814 S/N: M08663  
 Customer: CLEAN AIR INSTRUMENT RENTAL City: PALATINE State: IL  
 As-Received Model #: ADM-860C Converted to Model #: \_\_\_\_\_ Order #: R191507  
 PO #: \_\_\_\_\_ Customer Eqpt ID#: \_\_\_\_\_ Calibration Due Date: \_\_\_\_\_

This instrument has been calibrated using Calibration Standards which are traceable to NIST (National Institute of Standards and Technology). Test accuracy ratio is 4:1 for pressures and temperature. Quality Assurance Program and calibration procedures meet the requirements for ANSI/NCSL 2540-1, ISO 17025, MIL-STD 45662A and manufacturer's specifications. Calibration accuracy is certified when meters are used with properly functioning accessories only. All Uncertainties are expressed in expanded terms (twice the calculated uncertainty). This report shall not be reproduced, except in full, without the written approval of Shortridge Instruments, Inc. Results relate only to the item calibrated. For limitations on use, see Shortridge Instruments, Inc. Instruction Manual for the use of AirData Multimeters. Procedure used: Procedure for Differential Pressure, Absolute Pressure and Temperature Recalibration of AirData Multimeters SIP-CP02 Revision: 30 Dated: 04/04/16

Calibration Technician(s): UPR J. M. Arabach Calibration Date: 05/20/2019  
 Calibration Approved by: E. B. Babin Title: Technical Supervisor Date: 05/21/2019

AS-Received By: <u>UPR</u>	FINAL Test By: <u>JM</u>	Test By: _____
Date: <u>05-20-2019</u> Rh: <u>26</u> %	Date: <u>05/20/19</u> Rh: <u>28</u> %	Date: _____ Rh: _____ %
Ambient Temperature: <u>75</u> °F	Ambient Temperature: <u>75</u> °F	Ambient Temperature: _____ °F
Barometric Pressure: <u>28.25</u> in Hg	Barometric Pressure: <u>28.21</u> in Hg	Barometric Pressure: <u>NA</u> in Hg
All within spec: <u>(YES)</u> NO NA	All within spec: <u>(YES)</u> NO	All within spec: YES NO

### ABSOLUTE PRESSURE TEST (In Hg)

TEST METER TOLERANCE = ± 2.0 % ± .1 in Hg AS-RECEIVED TEST WITHIN SPEC (YES) NO N/A See Notes

Pressure Standard: Heise #02-R S/N: 41741/42451 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #12A-R S/N: 45605/48491 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #04-R S/N: 41743/42453 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #14-R S/N: 43412/45043-1 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #06-R S/N: 41742/42452-1 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #16-R S/N: 43413/45044 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #08-R S/N: 42186/43328 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #18-R S/N: 44581/46845 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #10-R S/N: 42203/43352 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #20-R S/N: 44582/46847 As-Rcvd Test 2 Test 3

Approx Set Pt	Standard	Test Meter	% Diff	Standard	Test Meter	% Diff	Standard	Test Meter	% Diff
14.0	14.00	13.8	-1.43	14.08	14.0	-.57			
28.4	28.25	28.2	-.18	28.21	28.1	-.39		NA	
40.0	40.00	39.9	-.25	40.16	40.1	-.15			

### DIFFERENTIAL PRESSURE TEST (In wc)

TEST METER TOLERANCE = ± 2.0 % ± 0.001 in wc AS-RECEIVED TEST WITHIN SPEC (YES) NO N/A See Notes

Pressure Standard: Heise #01-L S/N: 41739/42449 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #11-L S/N: 43165/44551-1 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #01-R S/N: 41739/42446 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #11-R S/N: 43165/44730 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #02-L S/N: 41741/42454 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #12A-L S/N: 45605/48490 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #03A-L S/N: 45570/48461 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #13-L S/N: 43415/45041 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #03A-R S/N: 45570/48460 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #13-R S/N: 43415/45039 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #04-L S/N: 41743/42456 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #14-L S/N: 43412/45045 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #05-L S/N: 41740/42450 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #15-L S/N: 43416/45042 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #05-R S/N: 41740/42447 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #15-R S/N: 43416/45040 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #06-L S/N: 41742/42455 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #16-L S/N: 43413/45046 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #07-L S/N: 42185/42186 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #17-L S/N: 44579/46842 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #07-R S/N: 42185/43326 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #17-R S/N: 44579/46841 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #08-L S/N: 42188/43329 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #18-L S/N: 44581/46846 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #09-L S/N: 42202/43351 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #19-L S/N: 44580/46844 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #09-R S/N: 42202/43350 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #19-R S/N: 44580/46843 As-Rcvd Test 2 Test 3
Pressure Standard: Heise #10-L S/N: 42203/43353 As-Rcvd Test 2 Test 3	Pressure Standard: Heise #20-L S/N: 44582/46848 As-Rcvd Test 2 Test 3

Approx Set Pt	Standard	Test Meter	% Diff	Standard	Test Meter	% Diff	Standard	Test Meter	% Diff
.0500	.0503	.0502	-.20	.0501	.0501	0			
.1250	.1250	.1255	-.08	.1259	.1258	-.06			
.2250	.2252	.2250	-.09	.2258	.2255	-.13			
1.000	1.027	1.028	.10	1.015	1.012	-.30			
2.000	2.050	2.047	-.15	2.015	2.015	0			
3.600	3.621	3.610	-.30	3.613	3.605	-.22			
4.400	4.409	4.419	.23	4.442	4.449	.16			
27.00	27.12	27.17	.18	27.50	27.54	.15			
50.00	50.32	50.28	-.08	50.65	50.56	-.18			
Overrange	NA	✓	NA	NA	✓	NA	NA	NA	NA

Shortridge Instruments, Inc.  
 7855 East Redfield Road Scottsdale, Arizona 85260  
 (480) 991-8744 • Fax (480) 443-1267 • www.shortridge.com



# AIRDATA MULTIMETER CERTIFICATE OF RECALIBRATION

S/N: M08663  
Order #: R191507

## LOW VELOCITY CONFIRMATION (FPM)

TEST METER TOLERANCE =  $\pm 3.0\% \pm 7$  FPM    AS-RECEIVED TEST WITHIN SPEC **(YES)** NO N/A See Notes

Vel Eqv Trans Std: S/N: M02009	As-Rcvd	Test 2	Test 3	Vel Eqv Trans Std: S/N: M10840	As-Rcvd	Test 2	Test 3
Vel Eqv Trans Std: S/N: M02803	As-Rcvd	<b>(Test 2)</b>	Test 3	Vel Eqv Trans Std: S/N: M10897	<b>(As-Rcvd)</b>	Test 2	Test 3
Vel Eqv Trans Std: S/N: M02903	As-Rcvd	Test 2	Test 3	Vel Eqv Trans Std: S/N: M10901	As-Rcvd	Test 2	Test 3
Vel Eqv Trans Std: S/N: M10839	As-Rcvd	Test 2	Test 3	Vel Eqv Trans Std: S/N: M13492	As-Rcvd	Test 2	Test 3

Approx Set Point	Standard	Test Meter	Diff	Standard	Test Meter	Diff	Standard	Test Meter	Diff
100	107	107	0	103	104	1			
500	526	527	1	503	502	-1		N/A	

ADM-880C, ADM-870/870C and ADM-860/860C models are read in AirFoil Mode. ADM-850/850L models are read in Pitot Tube Mode.

## TEMPERATURE TEST - AIRDATA MULTIMETER (° F)

TEST METER TOLERANCE =  $\pm 0.2^\circ$  F    AS-RECEIVED TEST WITHIN SPEC **(YES)** NO N/A See Notes

RTD Simulator: S/N 249	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 250	As-Rcvd	<b>(Test 2)</b>	Test 3	Set Point: 35.6° F	<b>(95° F)</b>	154.4° F
RTD Simulator: S/N 253	As-Rcvd	<b>(Test 2)</b>	Test 3	Set Point: 35.6° F	95° F	<b>(154.4° F)</b>
RTD Simulator: S/N 254	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 256	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 257	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 292	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 293	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 294	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 313	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 314	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 315	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 316	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 317	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F
RTD Simulator: S/N 318	As-Rcvd	Test 2	Test 3	Set Point: 35.6° F	95° F	154.4° F

RTD Simulator Temperature Equivalent Set Point	Test Meter	Difference	Test Meter	Difference	Test Meter	Difference
35.60	35.6	0	35.6	0		
95.00	94.8	-.2	94.8	-.2		
154.40	154.4	0	154.4	0		

NOTES: \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

The enclosed ADM Calibration Standards for Pressure and Temperature form(s) is/are an integral part of this calibration and must remain with this Certificate of Calibration. Note: There may be more than one such form included that pertains to this calibration.



**Shortridge Instruments, Inc.**  
7855 East Redfield Road Scottsdale, Arizona 85260  
(480) 991-6744 • Fax (480) 443-1267 • www.shortridge.com

# Shortridge Instruments, Inc. AirData Multimeter Calibration Equipment

Order Number: R191507      Serial Number: MD8663      Test Type:    Initial    As-Received    Final

### ABSOLUTE PRESSURE STANDARDS

ADM #02-R	S/N: 41741/42451	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 04/30/19	Due Date: 04/2020
ADM #04-R	S/N: 41743/42453	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 11/28/18	Due Date: 11/2019
ADM #08-R	S/N: 41742/42452-1	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 09/10/18	Due Date: 08/2019
ADM #08-R	S/N: 42186/43328	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 03/22/19	Due Date: 03/2020
ADM #10-R	S/N: 42203/43352	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 01/21/19	Due Date: 01/2020
ADM #12A-R	S/N: 45805/48491	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 07/31/18	Due Date: 07/2019
ADM #14-R	S/N: 43412/45043-1	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 09/28/18	Due Date: 09/2019
ADM #16-R	S/N: 43413/45044	Heise Model: PPM-2	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 02/20/19	Due Date: 02/2020
ADM #18-R	S/N: 44581/46845	Heise Model: PPM-2	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 05/08/18	Due Date: 05/2019
ADM #20-R	S/N: 44582/46847	Heise Model: PPM-2	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 06/08/18	Due Date: 06/2019
#02-R, 04-R, 06-R, 08-R, 10-R, 12A-R, 14-R, 16-R	Rated Accuracy: 0.05% fs (0.0305 in Hg)		Range: 0-30 psia		Resolution: 0.01	Uncertainty: < 0.0358
#18-R, 20-R	Rated Accuracy: 0.05% fs (0.0305 in Hg)		Range: 0-60 in Hg		Resolution: 0.001	Uncertainty: < 0.0358

### DIFFERENTIAL PRESSURE STANDARDS

ADM #01-L	S/N: 41739/42449	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 05/01/19	Due Date: 04/2020
ADM #01-R	S/N: 41739/42448	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 05/01/19	Due Date: 04/2020
ADM #02-L	S/N: 41741/42454	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 05/01/19	Due Date: 04/2020
ADM #03A-L	S/N: 45570/48461	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 11/28/18	Due Date: 11/2019
ADM #03A-R	S/N: 45570/48460	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 11/28/18	Due Date: 11/2019
ADM #04-L	S/N: 41743/42456	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 11/28/18	Due Date: 11/2019
ADM #05-L	S/N: 41740/42450	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 09/07/18	Due Date: 08/2019
ADM #05-R	S/N: 41740/42447	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 09/13/18	Due Date: 08/2019
ADM #06-L	S/N: 41742/42455	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 09/07/18	Due Date: 08/2019
ADM #07-L	S/N: 42185/42186	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 03/26/19	Due Date: 03/2020
ADM #07-R	S/N: 42185/43326	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 03/26/19	Due Date: 03/2020
ADM #08-L	S/N: 42186/43329	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 03/25/19	Due Date: 03/2020
ADM #09-L	S/N: 42202/43351	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 01/23/19	Due Date: 01/2020
ADM #09-R	S/N: 42202/43350	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 01/23/19	Due Date: 01/2020
ADM #10-L	S/N: 42203/43353	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 01/23/19	Due Date: 01/2020
ADM #11-L	S/N: 43165/44551-1	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 08/07/18	Due Date: 07/2019
ADM #11-R	S/N: 43165/44730	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 08/08/18	Due Date: 07/2019
ADM #12A-L	S/N: 45805/48490	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 07/30/18	Due Date: 07/2019
ADM #13-L	S/N: 43415/45041	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 10/03/18	Due Date: 09/2019
ADM #13-R	S/N: 43415/45039	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 10/04/18	Due Date: 09/2018
ADM #14-L	S/N: 43412/45045	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 10/02/18	Due Date: 09/2019
ADM #15-L	S/N: 43416/45042	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 02/22/19	Due Date: 02/2020
ADM #15-R	S/N: 43416/45040	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 02/22/19	Due Date: 02/2020
ADM #16-L	S/N: 43413/45046	Heise Model: PPM-1	Mfgd by Dresser Industries	Calibrated by Ashcroft	Calibration Date: 02/21/19	Due Date: 02/2020
ADM #17-L	S/N: 44579/46842	Heise Model: PPM-1	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 05/10/18	Due Date: 05/2019
ADM #17-R	S/N: 44579/46841	Heise Model: PPM-1	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 05/11/18	Due Date: 05/2019
ADM #18-L	S/N: 44581/46846	Heise Model: PPM-1	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 05/09/18	Due Date: 05/2019
ADM #19-L	S/N: 44580/46844	Heise Model: PPM-1	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 06/15/18	Due Date: 06/2019
ADM #19-R	S/N: 44580/46843	Heise Model: PPM-1	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 06/18/18	Due Date: 06/2019
ADM #20-L	S/N: 44582/46848	Heise Model: PPM-1	Mfgd & Calibrated by Ashcroft, Inc.		Calibration Date: 06/15/18	Due Date: 06/2019
#01-L, 03A-L, 05-L, 07-L, 09-L, 11-L, 13-L, 15-L, 17-L, 19-L	Rated Accuracy: > 0.07% fs (0.000175 in wc)		Range: 0.0-0.25 in wc		Res.: 0.00001	Uncertainty: < 0.00035
#01-R, 03A-R, 05-R, 07-R, 09-R, 11-R, 13-R, 15-R, 17-R, 19-R	Rated Accuracy: > 0.06% fs (0.003 in wc)		Range: 0.0-5.0 in wc		Res.: 0.0001	Uncertainty: < 0.00348
#02-L, 04-L, 06-L, 08-L, 10-L, 12A-L, 14-L, 16-L, 18-L, 20-L	Rated Accuracy: > 0.06% fs (0.03 in wc)		Range: 0.0-50.0 in wc		Res.: 0.001	Uncertainty: < 0.0346



**Shortridge Instruments, Inc.**  
 7855 East Redfield Road Scottsdale, Arizona 85260  
 (480) 991-6744 • Fax (480) 443-1267 • www.shortridge.com

## Shortridge Instruments, Inc. AirData Multimeter Calibration Equipment

Customer Order Number, Meter Serial Number, and Test Type are referenced on page 1

### LOW VELOCITY EQUIVALENT CONFIRMATION STANDARDS

Vel Eqv Transfer Standard S/N: M02009	Model ADM-870C	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 12/07/18	Due Date: 12/2019
Vel Eqv Transfer Standard S/N: M02803	Model ADM-870C	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 04/22/19	Due Date: 01/2020
Vel Eqv Transfer Standard S/N: M02903	Model ADM-870C	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 12/07/18	Due Date: 12/2019
Vel Eqv Transfer Standard S/N: M10839	Model ADM-870C	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 12/07/18	Due Date: 12/2019
Vel Eqv Transfer Standard S/N: M10840	Model ADM-870C	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 12/07/18	Due Date: 12/2019
Vel Eqv Transfer Standard S/N: M10887	Model ADM-870C	Mfg'd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 01/17/19	Due Date: 01/2020
Vel Eqv Transfer Standard S/N: M10901	Model ADM-870C	Mfg'd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 12/07/18	Due Date: 12/2019
Vel Eqv Transfer Standard S/N: M13492	Model ADM-870C	Mfg'd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 08/15/18	Due Date: 08/2019
Rated Accuracy: Velocity $\pm 1.5\% \pm 3.5$ fpm		Range: 100-5000 fpm    Resolution: 0.1	Uncertainty: <5.00 fpm at 100 fpm; <7.50 fpm at 500 fpm	

### TEMPERATURE STANDARDS

RTD Simulator S/N: 249	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 03/16/18	Due Date: 03/2020
RTD Simulator S/N: 250	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 03/16/18	Due Date: 03/2020
RTD Simulator S/N: 253	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 03/16/18	Due Date: 03/2020
RTD Simulator S/N: 254	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 04/07/18	Due Date: 04/2020
RTD Simulator S/N: 256	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 04/07/18	Due Date: 04/2020
RTD Simulator S/N: 257	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 04/07/18	Due Date: 04/2020
RTD Simulator S/N: 292	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 12/21/15	Due Date: 12/2019
RTD Simulator S/N: 293	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 12/21/15	Due Date: 12/2019
RTD Simulator S/N: 294	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 12/21/15	Due Date: 12/2019
RTD Simulator S/N: 313	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 03/16/18	Due Date: 03/2022
RTD Simulator S/N: 314	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 03/16/18	Due Date: 03/2022
RTD Simulator S/N: 315	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 03/16/18	Due Date: 03/2022
RTD Simulator S/N: 316	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 04/16/18	Due Date: 04/2022
RTD Simulator S/N: 317	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 04/16/18	Due Date: 04/2022
RTD Simulator S/N: 318	Model RTD-1000/500	Mfgd by General Resistance	Calibrated by IET Labs	Calibration Date: 04/16/18	Due Date: 04/2022
Rated Accuracy: 0.025% of setting		Range: 100.00 $\Omega$ to 11111.10 $\Omega$	Resolution: 0.01 $\Omega$	Uncertainty: $\leq 32$ ppm	

Thermometer #1 S/N 8A089/Thermistor S/N A410650	Model 1504/5810	Mfgd by Hart Scientific	Calibrated by Fluke	Calibration Date: 08/18/17	Due Date: 08/2019
Thermometer #2 S/N 8B104/Thermistor S/N 871507	Model 1504/5810	Mfgd by Hart Scientific	Calibrated by Fluke	Calibration Date: 11/07/18	Due Date: 10/2020
Thermometer #5 S/N B11780/Thermistor S/N B10505	Model 1504/5810	Mfgd by Hart Scientific	Calibrated by Fluke	Calibration Date: 03/07/19	Due Date: 03/2021
Thermometer #8 S/N B11782/Thermistor S/N B10509	Model 1504/5810	Mfgd by Hart Scientific	Calibrated by Fluke	Calibration Date: 02/20/18	Due Date: 02/2020
Thermometer #7 S/N B49938/Thermistor S/N B482202	Model 1504/5810	Mfgd and Calibrated by Fluke		Calibration Date: 09/26/17	Due Date: 09/2019
Rated Accuracy(combined): 0.0324° F		Range: 32° F to 176° F	Resolution: 0.001° F	Combined Uncertainty with Baths: $\leq 0.040$ ° F	

Temp Transfer Standard S/N M00136	Model ADM-870	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 10/04/18	Due Date: 10/2019
Temp Transfer Standard S/N M96100	Model ADM-870	Mfgd & Calibrated by Shortridge Instruments, Inc.	Calibration Date: 03/07/19	Due Date: 03/2020
Rated Accuracy: 0.03° F		Range: 33° F to 158° F	Resolution: 0.01° F	Uncertainty: < 0.023° F
Total combined Uncertainty for MultiTemp and TempProbe testing : $\leq 0.046$ ° F				

This form must remain with the Certificate of Calibration corresponding to the Customer Order Number and Meter Serial Number referenced on page 1.



**Shortridge Instruments, Inc.**  
 7855 East Redfield Road Scottsdale, Arizona 85260  
 (480) 991-6744 • Fax (480) 443-1267 • www.shortridge.com



### Oemga HHF142B-V Vane Anemometer

#### Rental and Application Notes

- Shipping Weight: ~ 10 lbs.
- High-quality instrument providing accurate air velocity and volume flow measurements
- Automatically calculates the volume flow rate from the duct
- The duct size is automatically stored in memory on turn-off and up to 10 unique duct sizes can be stored and recalled for frequent use.
- Optional umbilical extension and support rods are available upon request



	Specifications
<b>Weight</b>	2lbs
<b>Dimensions</b>	16.5" x 3.25" x 1.5"
<b>Power</b>	3 "AA" alkaline batteries
<b>Range</b>	0.2 to 40.00 MPS (40 to 7800FPM)
<b>Accuracy</b>	+/- 1% of reading / + 1 Digits
<b>Outputs</b>	0 - 5 V analog signal
<b>Operating Temperature</b>	0° C to 50° C (32° F to 122° F) Probe: -20° C to 100° C (-4° F to 212° F)
<b>Probe Diameter</b>	2.75"
<b>Battery</b>	NiMH rechargeable pack 4.8V max
<b>Display</b>	0.5" LCD, 4 -digits



# Certificate of Calibration



15256195

Certificate Page 1 of 2

## Instrument Identification

Company ID: 77065  
CLEAN AIR INSTRUMENT RENTALS  
GARY ZAPEL  
500 WEST WOOD ST.  
PALATINE, IL 60067

PO Number: 65675 70 65800

Instrument ID: **208871**  
Manufacturer: OMEGA  
Description: VANE ANEMOMETER

Model Number: HHF142  
Serial Number: 1017702

Accuracy:  $\pm 1\%$  of reading,  $\pm 1$  digit.

## Certificate Information

Reason For Service: CALIBRATION

Type of Cal: NORMAL

As Found Condition: IN TOLERANCE

As Left Condition: IN TOLERANCE

Procedure: 33K6-4-1769-1 VELOCITY, TEMP, AND FLOW REV:  
9/30/15

Remarks:

Technician: RYAN EDWARDS

Cal Date 03Jan2020

Cal Due Date: 03Jan2021

Interval: 12 MONTHS

Temperature: 23.0 C

Humidity: 34.0 %

Tektronix certifies the performance of the above instrument has been verified using test equipment of known accuracy, which is traceable to the International System of Units (SI), National Metrology Institutes (NIST, NPL, PTB), derived from ratio type measurements, compared to reference materials or recognized consensus standards. The policies and procedures comply with ANSI/NCSL Z540.1-1994. The quality system complies with ISO9001.

This certificate shall not be reproduced, except in full, without the written consent of Tektronix.



Approved By: RYAN EDWARDS  
Service Representative

Issue Date: 1/3/2020

## Calibration Standards

NIST Traceable#	Inst. ID#	Description	Manufacturer	Model	Cal Date	Date Due
14842883	38-1005980	PITOT TUBE AIRFLOW SYSTEM	SYPRIS	AF12319/PX653	16Aug2019	16Feb2021
14330222	38-1018828	TEMP/HUMIDITY PROBE	VAISALA	HMP45A	30Jan2019	30Jan2020
14333248	38-1037024	BAROMETRIC TRANSDUCER	OMEGADYNE	PX02K1-28A5T	31Jan2019	31Jan2020

9639 Interoccean Drive • Cincinnati, OH 45246 • Phone: 513-870-4730 • Fax: 513-874-7752





# Certificate of Calibration



15256195

Certificate Page 2 of 2

## Calibration Standards

<u>NIST Traceable#</u>	<u>Inst. ID#</u>	<u>Description</u>	<u>Manufacturer</u>	<u>Model</u>	<u>Cal Date</u>	<u>Date Due</u>
14302838	B0023974	DATA ACQUISITION/SWITCH UNIT	AGILENT	34970A	22Jan2019	22Feb2020
15123132	C100008	HIGH ACCURACY PRESSURE TRANSDUCER	MKS INSTRUMENTS	120AD-00001RCU	30Oct2019	30Apr2021
14550342	H058567	DIGITAL PRESSURE GAGE	MENSOR	2101	09Apr2019	08Jun2020





## Product Information

### Description

The Bosch BLAZE™ GLM 42 135 Ft. Laser Measure is a fully featured, easy-to-use tool, with a display guide that uses words, letters and icons to walk the user through each measurement process. The easy-to-read backlit color display improves the visibility and usability of the laser measure. It provides real-time length, length, area, volume and indirect measuring functions, and it has a 20-measurement storage capability and addition/subtraction functionality. This tool includes default real-time measurement mode, adjusting the measurement the closer to or further from the target the laser measure is. The digital bubble vial provides a visual reference when measuring horizontal distances. Thanks to its laser precision technology and real-time measurement mode, it takes instant and reliable measurements up to 135 Ft., to size up the job in seconds. It is accurate up to  $\pm 1/16$  In. And it fits in any pocket for easy access.

- Easy-to-read backlit color display – illuminates numbers in dark areas with resolution, allowing work in low-light conditions
- Default real-time measurement mode – provides accurate measurement that automatically adjusts closer to or farther from the target
- Easy-to-use display guide - walks the user through each measurement process
- Multiple measuring features – includes real-time length, length, area, volume and indirect functions, and addition/subtraction capability

- Memory storage – provides storage for up to 20 measurements
- Accuracy and long-range measuring – provides accuracy up to 1/16 In. and measures up to a 135 Ft. range
- Digital bubble level – provides a visual reference when measuring horizontal distances
- Compact size – fits in any pocket for easy access

## **Specifications**

<b>Sub-Brand</b>	BLAZE
<b>Series Name</b>	N/A
<b>Minimum Distance (Feet)</b>	0
<b>Maximum Distance (Feet)</b>	135
<b>Accuracy at Maximum Distance</b>	1/16-in
<b>Backlit Display</b>	Yes
<b>Belt Clip</b>	No
<b>Rechargeable</b>	No
<b>Battery Type</b>	Alkaline
<b>Batteries Included</b>	Yes
<b>Case Included</b>	Yes
<b>Warranty</b>	2-year
<b>Use Location</b>	Outdoor
<b>Wi-Fi Compatibility</b>	No
<b>Works with iOS</b>	No
<b>App Compatibility</b>	No
<b>UNSPSC</b>	27111800
<b>Works with Android</b>	No
<b>Bluetooth Compatibility</b>	No
<b>Hand Strap Included</b>	Yes

**This Page Intentionally Left Blank**

## APPENDIX B: NE EVALUATION DATA SHEETS

**This Page Intentionally Left Blank**

**Area of NDO's**

<u>NDO ID</u>	<u>NDO Description</u>	<u>NDO Dimensions</u>	<u>NDO Area (ft<sup>2</sup>)</u>
1) A-1	North end mandoor louver	22" x 22"	3.36
2) A-2	Ceiling louver	4' x 4'	16.0
3) B-1	Ceilcote scrubber room drainage	2 x 5" x 1" + 2 x 8" x 1" + 1 x 9" x 1"	0.07 + 0.11 + 0.06 <hr/> 0.24
4) B-2	Ceilcote scrubber room wall louver	4' x 4'	16.0
5) C-1	Dock 16 shipping door with truck	2 x 1" x 10' + 1 x 4.5" x 9'	1.67 + 3.38 <hr/> 5.05
6) C-2	Dock 17 shipping door with truck	2 x 1" x 10' + 1 x 4.5" x 9'	1.67 + 3.38 <hr/> 5.05
<b>Total NDO Area =</b>			<b>45.70</b>

**Surface Area of Enclosure**

<u>Surface Area Description</u>	<u>Surface Area Dimensions</u>	<u>SA Area (ft<sup>2</sup>)</u>
<b>Zone A</b>		
Floor	$(87' \times 172') - (4' \times 3') - (6' \times 12') - (20' \times 38')$	14120
Ceiling	$(87' \times 172') - (4' \times 3') - (6' \times 12') - (20' \times 38')$	14120
North Wall	87' x 24'	2088
South Wall	87' x 24'	2088
East Wall	$((49' + 3' + 120' - 8.5' - 20') \times 24') + (20' \times 13.5')$	3714
West Wall	$(152' \times 24') + (14' \times 13.5') + (6' \times 13.5')$	3918
<b>Zone B</b>		
Floor	5081' + (120' x 54)	11561
Ceiling	5081' + (120' x 54)	11561
North Wall	$(41' \times 24') + (25' \times 24') + (120' \times 24')$	4464
South Wall	$(43' \times 24') + (154' \times 24')$	4728
East Wall	$(37.5' \times 24') + (6.5' \times 24')$	1056
West Wall	54' x 24'	1296
<b>Zone C</b>		
Floor	$(195' \times 123') + ((22' \times 47') + (1/2 \times 3' \times 47'))$	25090
Ceiling	$(195' \times 123') + ((22' \times 47') + (1/2 \times 3' \times 47'))$	25090
North Wall	$(123' \times 24') + (22' \times 68')$	4448
South Wall	$(123' \times 24') + (25' \times 68')$	4652
East Wall	$195' \times 24' + (21' \times (28 - 24')) + (26' \times (68' - 24'))$	5908
West Wall	$195' \times 24' + (21' \times (28 - 24')) + (26' \times (68' - 24')) - (19.5' \times 24')$	5440
<b>Total Surface Area of Enclosure =</b>		<b>145342</b>
<b>Total Surface Area of Enclosure Minus Total NDO Area =</b>		<b>145296.30</b>
<b>NEAR =</b>		<b>0.031%</b>

*[Signature]* 3/24/20

# NDO Directional Flow Datasheet

Client: Sterigenics  
 Project No: 14004  
 Unit: Production - 41A 1  
 Method of verification: Tracer Tubes

Facility: Atlanta  
 Date: 3/24/20  
 Start Time: 13:00 Stop Time: 14:00  
 Operator: Kenny Sullivan

Notes: all IN, observations made with smoke tubes

NDO ID	Time/Direction						Notes
C-1	13:00/in	1310/in	1320/in	1330/in	1340/in	1350/in	Deck 16
C-2	13:01/in	1311/in	1321/in	1331/in	1341/in	1351/in	Deck 17
B-1	13:02/in	1312/in	1322/in	1332/in	1342/in	1352/in	Ceiling Damage
B-2	13:03/in	1313/in	1323/in	1333/in	1343/in	1353/in	Ceiling Lower
A-1	13:05/in	1314/in	1324/in	1334/in	1344/in	1355/in	Manhole Lower
A-2	13:07/in	1316/in	1326/in	1337/in	1347/in	1357/in	Ceiling Lower
<p><del>*</del> All observations were IN</p>							



QA/QC  
 Date: 3/24/20



# NE Pressure Drop Datasheet

Client: Sterigenics  
 Project No: 14004  
 Unit: Production IA-1  
 Instrument: Shortridge microManometer

Facility: Atlanta  
 Date: 3/24/20  
 Start Time: 1420 Stop Time: 15:40  
 Operator: Kenny Sullivan

Notes:

Ref pressure = <sup>typical</sup> tube ran outside facility i.e. ambient pressure.

NE Area	Time/Δp					Notes
<del>Zone A</del> <sup>vs 3/24</sup>	1420	1438	1441	1444	1447	<del>manometer #</del>
Zone B - Corridor	1 - 0.0247	1 - 0.0224	1 - 0.0227	1 - 0.0354	1 - 0.0391	New Chamber 6 Transfer Corridor
	2 - 0.0197	2 - 0.0220	2 - 0.0320	2 - 0.0419	2 - 0.0375	
	3 - 0.0206	3 - 0.0252	3 - 0.0310	3 - 0.0280	3 - 0.0120	
	4 - 0.0217	4 - 0.0308	4 - 0.0255	4 - 0.0326	4 - 0.0231	
	5 - 0.0186	5 - 0.0290	5 - 0.0380	5 - 0.0371	5 - 0.0275	
Avg	-0.0211	-0.0270	-0.0324	-0.0360	-0.0278	<u>-0.0284</u>
<del>Zone B</del> <sup>vs</sup> Corridor	1420	1423	1426	1429	1432	
Zone A	1 - 0.0429	1 - 0.0592	1 - 0.0341	1 - 0.0396	1 - 0.0489	Transfer Corridor manometer near Chamber 6
	2 - 0.0352	2 - 0.0558	2 - 0.0500	2 - 0.0378	2 - 0.0510	
	3 - 0.0329	3 - 0.0566	3 - 0.0459	3 - 0.0443	3 - 0.0490	
	4 - 0.0394	4 - 0.0486	4 - 0.0476	4 - 0.0452	4 - 0.0502	
	5 - 0.0441	5 - 0.0418	5 - 0.0470	5 - 0.0467	5 - 0.0462	
Avg	-0.0390	-0.0540	-0.0451	-0.0427	-0.0442	<u>-0.0460</u>
Zone B - Corridor	1450	1453	1456	1459	1502	
Terminus just outside warehouse NAD	1 - 0.0153	1 - 0.0334	1 - 0.0216	1 - 0.0475	1 - 0.0086	Corridor Scrubber Room
	2 - 0.0082	2 - 0.0150	2 - 0.0197	2 - 0.0078	2 - 0.0037	
	3 - 0.0085	3 - 0.0403	3 - 0.0141	3 - 0.0178	3 - 0.0164	
	4 - 0.0027	4 - 0.0158	4 - 0.0305	4 - 0.0196	4 - 0.0061	
	5 - 0.0090	5 - 0.0122	5 - 0.0145	5 - 0.0068	5 - 0.0032	
Avg	-0.0078	-0.0173	-0.0195	-0.0200	-0.0078	<u>-0.0143</u>
						Terminus out the manometer



# NE Pressure Drop Datasheet

Client: Sterigenics  
 Project No: 14004  
 Unit: Production - I#-1  
 Instrument: Shortridge Micromanometer

Facility: Atlanta  
 Date: 3/24/20  
 Start Time: 14:20 Stop Time: 15:40  
 Operator: Kenny Sullivan

Notes:

NE Area	Time/Δp						Notes
Zone C <sub>1</sub> - Shipping/operation corrh	1507	1510	1513	1516	1519		Shipping area AHEAD RACKS
	1 -0.0137	-0.0141	-0.0139	-0.0028	-0.0055		
	2 -0.0076	-0.0213	-0.0093	-0.0046	-0.0106		
	3 -0.0043	-0.0180	-0.0099	-0.0034	-0.0142		
	4 -0.0122	-0.0207	-0.0137	-0.0062	-0.0072		
	5 -0.0113	-0.0149	-0.0156	-0.0069	-0.0116		
Avg	-0.0102	-0.0175	-0.0125	-0.0048	-0.0092	-0.0108	
Zone C - NAT	1525	1529	1531	1534	1537		NAT Sandals Room
	1 -0.0456	1 -0.0795	1 -0.0761	1 -0.0546	1 -0.0385		
	2 -0.0409	2 -0.0570	2 -0.0334	2 -0.0515	2 -0.0262		
	3 -0.0356	3 -0.0696	3 -0.0386	3 -0.0473	3 -0.0389		
	4 -0.0524	4 -0.0421	4 -0.0573	4 -0.0436	4 -0.0385		
	5 -0.0521	5 -0.0554	5 -0.0555	5 -0.0489	5 -0.0498		
Avg	-0.0457	-0.0607	-0.0441	-0.0485	-0.0404	-0.0473	




QA/QC  
Date 3/24/20

## APPENDIX C: NDO LOG AND SKETCHES

**This Page Intentionally Left Blank**

# NDO Log Datasheet

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 3/24/20	
Initials: 	

NDO Identification No.	NDO Description/Dimensions	Total Area (ft <sup>2</sup> )	Notes
A-1	Mandator Louver behind Chamber #7, 27" x 22", Zone A	3.36	
A-2	Zone A South side Ceiling Louver, 4' x 4'	16.0	
B-1	Zone B Curbide Scrubber Room drain trap outlet, (see notes)	0.24	area under traps: 2x5"x1", 2x5"x1", 1x9"x1"
B-2	Zone B Curbide Scrubber Room Post wall Louver, 4' x 4'	16.0	area under traps: 2x5"x1", 2x5"x1", 1x9"x1" - approximately
C-1	Zone C Dock 16 shipping door, (see notes)	5.05	area not sealed: 2x1'x10', 1x9.5"x9'-J
C-2	Zone C Dock 17 shipping door, (see notes)	5.05	area not sealed: 2x1'x10', 1x9.5"x9'-J

QA/QC   
Date 3/24/20




# NDO Sketch Datasheet

Location: North Well Chemistry Room Zone A

Client: Sterigenics	Project No: 14004
Plant: Atlanta	Surface Name(s): Zone A Well
Date: 2/19/20	Initials: <i>[Signature]</i>

Notes: NDO A-1, Main floor level 22" x 22"  
Located North wall, Zone A, Near chamber #7

Indicate location & NDO Id.



Orientation/Scale:

QA/QC *[Signature]*  
 Date 3/24/20



# NDO Sketch Datasheet


Location: Zone A Ceiling (SE Corner)

Client: Sterigenics	Project No: 14004
Plant: Atlanta	Surface Name(s): Zone A, ceiling
Date: 3/24/12	
Initials: <i>[Signature]</i>	

Notes: NDO ID A-2

Ceiling Louver 4' x 4', Near Southeast corner

Indicate location & NDO Id.



Orientation/Scale:

# NDO Sketch Datasheet


Location: Zone B Ceiling Room

Client: Sterigenics	Project No: 14004
Plant: Atlanta	Surface Name(s):
Date: 3/24/20	Zone B, South Wall
Initials: <i>[Signature]</i>	Ceiling Room

Notes: NDO B-1

Ceiling scrubber Room, South wall, drainage opening

Indicate location & NDO id.



Orientation/Scale:




# NDO Sketch Datasheet

Location: Zoo B Center Room

Client: Sterigenics	Project No: 14D04
Plant: Atlanta	Surface Name(s):
Date: <u>3/24/20</u>	<u>East Wall, Corridor</u>
Initials: <u>[Signature]</u>	

Notes: Ab B-2 Wall Layer 4' x 2'

Indicate location & NDO id.



Orientation/Scale:


# NDO Sketch Datasheet

Location: North Wall Dock 16 Zone C

Client: Sterigenics	Project No: 14004
Plant: Atlanta	Surface Name(s):
Date: 3/24/20	North wall zone C
Initials: <i>JA</i>	shipping area

Notes: Use C-1 Shipping door @ Dock 16 with truck at dock  
NDO = openings around truck gaps

Indicate location & NDO Id.



Orientation/Scale:

QA/QC *[Signature]*  
 Date 3/24/20




# NDO Sketch Datasheet

Location: Nashville Dock 17 Zone C

Client: Sterigenics	Project No: 14004
Plant: Atlanta	Surface Name(s):
Date: 3/24/20	<u>Northwell Zone C</u>
Initials: <u>EA</u>	<u>Shipping Area</u>

Notes: No C-2 shipping door @ Dock 17 with truck @ Dock  
Also = openings around truck gaps

Indicate location & NDO Id.



Orientation/Scale:

QA/QC EA  
 Date 3/24/20

**This Page Intentionally Left Blank**


## APPENDIX D: NE AREA WALL SKETCHES

**This Page Intentionally Left Blank**

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location:	North Wall Chamber Room (Zone A)	
Client:	Sterigenics	Project No: 14004
Plant:	Atlanta	
Date:	2/19/20	
Initials:	<i>[Signature]</i>	

Notes: 2 MDO's: Fan Louver ↓ bear Louver  
KHS - Not MDO (forced draft)




QA/QC *[Signature]*  
 Date 2/19/20

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: South Wall Chamber Room (Zone A)

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 2/19/20	
Initials: JS	

Notes: - Strip curtain used for EO drum transfer  
 - Garage door remains closed upon no EO drum transfer  
 - Other door remains closed



Orientation/Scale: Facing South

QA/QC Date: 2/19/20




# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: East Wall Chamber Room (Zona)

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 7/17/20	
Initials: <u>JA</u>	

Notes: - Right side (south) part of Sust. Area for NBAR  
 - Garage door = Speed door



Orientation/Scale: Facing East


# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: West Wall Chamber Room (Zone A)

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 4/9/20	
Initials: <i>AB</i>	

Notes: N's NRO's

Garage Door Remains closed (used for adding/removing Chambers)




Date 7/19/20

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: North Wall Zone B

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 7/28/20	
Initials: <u>BA</u>	

Notes: No NBO's




Orientation/Scale: Facing North

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location:	South Wall Zone B	Project No:	14004
Client:	Sterigenics	Plant:	Atlanta
Date:	3/24/20	Initials:	HA

Notes: 2 AMO: Concrete Sump Room Damage Assessed



Orientation/Scale:  
Looking South


# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: East Wall Zone B Project No: 14004

Client: Sterigenics Plant: Atlanta

Date: 3/24/20 Initials: PS

Notes: 7 AHO: Concrete Scrubber Wall Corner



Orientation/Scale: Facing East


QA/QC  
Date: 3/24/20

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: West Wall Zone B

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 2/24/20	
Initials: <i>[Signature]</i>	

Notes: No MCO's




Orientation/Scale: Looking West

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: North Wall Zone C (Sampling)

Client:	Sterigenics	Project No.:	14004
Plant:	Atlanta		
Date:	3/24/20		
Initials:	<i>JD</i>		

Notes: 2 NMO's - Deck 16 & 17 track seal gaps



QA/QC *JD*  
 Date 3/24/20

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet


Location: South Wall Zone C Project No.: 14004

Client: Sterigenics Plant: Atlanta

Date: 3/24/20

Initials: MAO's

Notes:



QA/QC  
Date: 3/24/20




# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: East Wall Zone C

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: <u>3/24/20</u>	
Initials: <u>[Signature]</u>	

Notes: No MO's




QA/QC: [Signature]  
Date: 3/24/20

# Enclosure Floor/Wall/Ceiling Plan - Sketch Datasheet

Location: West Wall Zoned

Client: Sterigenics	Project No: 14004
Plant: Atlanta	
Date: 2/24/20	
Initials: <i>[Signature]</i>	

Notes: As MGS



QA/QC: *[Signature]*  
Date: 2/24/20

## APPENDIX E: CLEANAIR RESUMES AND CERTIFICATIONS

**This Page Intentionally Left Blank**

## Ken Sullivan Project Manager

### Professional Profile

---

Mr. Sullivan has 10 years of experience in wet method and instrumental testing for engineering, diagnostic, performance guarantee, and compliance purposes. Initially hired as a field technician in 2009, Mr. Sullivan started leading test programs in 2011, and has been project managing since 2014. Mr. Sullivan has been involved with projects utilizing EPA Methods 1 through 29, 201, 201A, 202, 320, Conditional Test Method (CTM) 027, CTM-013, and Other Test Methods (OTM) 027 and OTM-028, from the planning stage to field testing and reporting. In addition, Mr. Sullivan has extensive experience leading Engineers and Field Technicians to execute applicable EPA methods for numerous projects worth hundreds of thousands of dollars to clients. Through his experience, he has attained valuable testing skills, such as setting up and operating continuous emissions monitoring systems (CEMS) for various pollutants, on-site mercury analysis with an Ohio Lumex spectrometer, on-site laboratory analysis for numerous methods, experience in Micro GC (gas chromatography), and in FTIR (Fourier Transform Infrared Spectrometer) analysis.

Mr Sullivan has been responsible for compliance and diagnostic test programs performed in a multitude of states across the country. He has also been responsible for engineering and consulting studies performed in Canada, Netherlands, Spain, and South Africa.

### Relevant Experience

---

#### Coal Industry; Labadie and Meramec, MO

Led a large field crew in executing various EPA methods, including 30B, 5/202, 29, 26, 3A, 7E, and 10 at multiple locations to determine design variables for retrofitted wet scrubbers. Set-up and operated a CEMS showing real-time NO<sub>x</sub>, O<sub>2</sub>, CO<sub>2</sub>, and CO emissions. Performed on-site mercury analysis with an Ohio Lumex spectrometer in accordance with EPA Method 30B. Assisted in determining the concentration deviation between elemental and oxidized mercury at the stack to establish scrubber performance, carbon injection interference, and other design constraints.

#### Natural Gas Delivery (Pipeline); Middlebourne, WV

Project managed a test program to determine sources and locations of black powder along various points of the pipeline, by utilizing a personally designed modified EPA Method 17 sampling apparatus. Led field execution, collected samples and recovered sample filters on-site while maintaining communication with the client and several other parties involved to resolve the issue of equipment malfunction and degradation due to the black powder buildup.

#### Manufacturing Industry; Apeldoorn, Netherlands

Planned, managed, led, and executed this job from start to finish. Ran an FTIR and performed EPA Methods 320 and 25A to provide the client with carbon monoxide, hydrocarbon, and formaldehyde diagnostic data at several key points along the process line. Processed and analyzed a plethora of raw data into utile and interpretable formats and drafted an in-depth report.

### Carbon Capture; Cohasset, MN

Project managed a test program designed to determine the input/output chemistry of a non-commercial scale carbon capture system prototype. The test program included measurements for over 20 compounds of interest, utilizing FTIR, GC-FPD, Micro GC, FID, UV, and photometric technologies. Developed extensive analysis that included studies in atom balance, removal, minimum detection limit, and exponential decay.

### Coal Industry; Secunda, South Africa

Aided in accumulating dust concentration data and mass loading at various points in the Fluidized Catalytic Cracking Unit (FCCU), utilizing EPA Method 17. Was involved in on-site recovery and particle size analysis, and used a TESTO 350XL to determine effluent gas composition. Also trained a South African testing company how to efficiently and accurately execute methods concerning filterable particulate matter (FPM) collection.

### Oil Refining Industry; Detroit, MI

Aided multi-million net-worth client in meeting new emission limits required by a permit issued by the Michigan Department of Environmental Quality (MDEQ) and Sierra Club due to implications of the Detroit Heavy Oil Upgrade Project (DHOUP). Executed several different methods, including EPA Methods 1, 2, 3A, 4, 5/202, 6C, 7E, 25A, 10, and 18, and ASTM Draft CCM, at various locations throughout the Detroit refinery. Managed every test program from planning to reporting.

## Professional Certifications & Qualifications

OSHA 10-Hour

NSC CPR/AED Certification

NSC First-Aid Certification

Qualified Source Testing Individual (QSTI) Test Exams (Certificate No. 2012-711):

- Group 1 (Manual Gas Volume and Flow Measurements and Isokinetic Particulate Sampling Methods) – exam passed on 10/22/2015 (certification attached)
- Group 2 (Manual Gaseous Pollutants Source Sampling Methods) – exam passed on 4/28/2016 (certification attached)
- Group 3 (Gaseous Pollutants Source Sampling Methods) – exam passed on 4/27/2016 (certification attached)
- Group 4 (Hazardous Metals Measurement Methods) – exam passed on 6/1/2017 (certification attached)

Qualified Individual (QI)

Field Test Leader	Ohio Lumex (EPA Method 30B Analysis)	EPA Methods 320/321 (Extractive FTIR)	Field Laboratory
Project Manager	Modified EPA Conditional Test Method 013 / Draft ASTM Controlled Condensation Method		

## Education

---

Bachelor of Science in Civil Engineering with a focus in Environmental and Atmospheric Sciences (with honors), 2009

University of Illinois; Urbana-Champaign

Bachelor of Science in Physics, 2006

Elmhurst College; Elmhurst, Illinois

# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT

**KENNETH J. SULLIVAN**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

**MANUAL GAS VOLUME MEASUREMENTS AND ISOKINETIC PARTICULATE SAMPLING METHODS**

ISSUED THIS 22<sup>ND</sup> DAY OF OCTOBER 2015 AND EFFECTIVE UNTIL OCTOBER 21<sup>ST</sup>, 2020

Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board

Theresa Lowe, QSTI/QSTO Review Board

J. Wade Bice, QSTI/QSTO Review Board

Karen D. Kajiyva-Mills, QSTI/QSTO Review Board

Bruce Randall QSTI/QSTO Review Board



CERTIFICATE  
NO.

2012-711



# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual


LET IT BE KNOWN THAT

**KENNETH J. SULLIVAN**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

### **MANUAL GASEOUS POLLUTANTS SOURCE SAMPLING METHODS**

ISSUED THIS 28<sup>TH</sup> DAY OF APRIL 2016 AND EFFECTIVE UNTIL APRIL 27<sup>TH</sup>, 2021



Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board

Theresa Lowe, QSTI/QSTO Review Board

J. Wade Bice, QSTI/QSTO Review Board

Karen D. Kajjya-Mills, QSTI/QSTO Review Board

Bruce Randall QSTI/QSTO Review Board

CERTIFICATE  
NO.  
2012-711

# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT

**KENNETH J. SULLIVAN**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

**GASEOUS POLLUTANTS INSTRUMENTAL SAMPLING METHODS**

ISSUED THIS 27<sup>TH</sup> DAY OF APRIL 2016 AND EFFECTIVE UNTIL APRIL 26<sup>TH</sup>, 2021




  
Peter R. Westlin, QSTI/QSTO Review Board

  
Peter S. Pakalnis, QSTI/QSTO Review Board

  
Theresa M. Lowe, QSTI/QSTO Review Board

  
J. Wade Bice, QSTI/QSTO Review Board

  
Karen D. Kajjya-Mills, QSTI/QSTO Review Board

  
Bruce Randall, QSTI/QSTO Review Board

CERTIFICATE  
NO. 2012-711

# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT

**KENNETH J. SULLIVAN**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

### **HAZARDOUS METALS MEASUREMENT METHODS**

ISSUED THIS 1<sup>ST</sup> DAY OF JUNE 2017 AND EFFECTIVE UNTIL MAY 31<sup>ST</sup>, 2022






Peter R. Westlin, QSTI/QSTO Review Board



Peter S. Pakalnis, QSTI/QSTO Review Board



Theresa Lowe, QSTI/QSTO Review Board



J. Wade Bice, QSTI/QSTO Review Board



Karen D. Kajiya-Mills, QSTI/QSTO Review Board



Bruce Randall, QSTI/QSTO Review Board

CERTIFICATE

NO.

2012-711

## Bill Ansell

### Midwest Engineering Group Technical Leader and Sr. Project Manager

#### Professional Profile

---

Mr. Ansell has over 30 years of experience in the environmental field in the areas of air emissions testing and consulting. He was initially hired as a Field Engineer. Since 1988, Mr. Ansell has been involved with projects utilizing EPA, ASTM, NIOSH, ASME methods from the planning stage through field execution and reporting. In addition, Mr. Ansell has extensive process and control device knowledge across a variety of industries including:

- municipal and medical waste combustors;
- petrochemical industries and refineries;
- utility and institutional coal, oil, and natural gas-fired boilers;
- foundries and steel mills;
- simple and combined cycle gas turbines;
- printing and coating facilities;
- automotive assembly plants;
- glass plants;
- food processing facilities;
- ammunition plants; and
- pulp and paper mills, as well as other industrial sources.

Mr. Ansell was responsible for projects performed in 30 states as well as China, South Korea, Puerto Rico, Morocco, and the Bahamas.

#### Relevant Experience

---

##### Automotive Assembly Plant; Mishawaka, IN

Project Manager and Field Test Leader for a VOC capture and destruction efficiency test program conducted on the e-coat, prime, and topcoat paint lines at an automotive assembly plant. Project included verifying that enclosures surrounding paint lines met criteria for permanent and temporary total enclosures per EPA Method 204. VOC emissions from five sources to the control device, as well as fugitive VOC emissions from 16 sources, were determined simultaneously, following EPA Methods 1-4, 25A, and 204B. Tests were conducted with a nine-man test crew

##### Yeast Production Facility; Memphis, TN

Project Manager and Field Test Leader for annual VOC emission test programs to meet requirements of the facility's Title V Permit and 40 CFR 63, Subpart CCCC - National Emissions Standards for Hazardous Air Pollutants: Manufacturing of Nutritional Yeast. Client monitors brew ethanol concentrations during production instead of installing fermenter exhaust monitors. NESHAP requires testing to develop a brew to exhaust correlation calculation relating the brew ethanol concentration during fermentation to THC emissions concentration as propane. Test programs were conducted over complete production batches, 13 to 31 hours in duration requiring multiple test crews for 24-hour coverage on-site.

## Paper Mill; Rhinelander, WI

Project Manager and Field Test Leader for a VOC capture and destruction efficiency test program on a thermal oxidizer system serving a paper coater line. The test program included the construction of a temporary total enclosure (TTE), including a fugitive vent system to prevent VOC concentrations from building up within the enclosure, which surrounded the coater to allow the VOC capture efficiency to be determined and the process to be operated normally.

Project Manager and Field Test Leader for performance and compliance test programs on coal and natural gas-fired boilers, including the initial certification and annual RATA for SO<sub>2</sub>, NO<sub>x</sub>, CO, HCl, and PM CEMS, as well as sorbent trap mercury emissions testing.

## Coal-Fired Power Plant (Wet Scrubber); Huntington, UT

Project Manager and Field Test Leader for a wet flue gas desulfurization (FGD) system performance guarantee test program at a coal-fired power plant. The FGD test program included determining SO<sub>2</sub> emissions from the FGD system as well as determining overall FGD system pressure drop, stoichiometry ratio, gypsum oxidation level and percent solids dewatering. The sound pressure levels for new operating equipment related to the FGD system, including slurry pumps and ID Booster Fans, were measured as well.

Limestone slurry and gypsum slurry samples were collected and analyzed to determine reagent / byproduct quality, limestone consumption rates and scrubber stoichiometry. Preliminary particulate, SO<sub>2</sub> and SO<sub>3</sub> results were determined on-site.

## Coal-Fired Power Plant (SCR, ACI, Dry FGD); Big Stone City, ND

Project Manager and Field Test Leader for a boiler pressure part modification and separated over fire air (SOFA) system, dry flue gas desulfurization (DFGD) system, activated carbon injection (ACI) system, selective catalytic reduction (SCR) system, and centrifugal ID fan system performance guarantee test program on a coal-fired boiler. The boiler pressure and SOFA tests included measuring pressure losses, heat output, and unburned carbon. The SCR performance tests included measuring pressure loss, power consumption, SO<sub>2</sub>, SO<sub>3</sub>, NO<sub>x</sub> and ammonia emissions and ammonia distribution. The ACI system tests included measuring flue gas flow rate and composition, powdered activated carbon (PAC) injection rate, and sound pressure levels around ACI process equipment. The DFGD system tests included measuring flue gas flow rate and composition, filterable and condensable particulate matter (FPM and CPM), SO<sub>2</sub>, SO<sub>3</sub>, HCl, lime stoichiometry, power consumption, pressure loss, and sound pressure levels around specified DFGD equipment. The ID Fan performance tests included measuring flue gas temperatures, static and total pressures, and 3-D flow rates, including pitch and yaw angles and axial velocity.

The test program was conducted in a single mobilization using a 13-man test crew over an 11-day period. Preliminary analytical results for SO<sub>2</sub>, SO<sub>3</sub>, HCl, FPM, and ammonia were performed on-site by CleanAir personnel.

## Coal-Fired Power Plant (SNCR and SCR); Healy, AK

Project Manager and Field Test Leader for SCR and SNCR performance guarantee test programs on two coal-fired boilers: one with SNCR system and one with SCR system. The SNCR test program included determining ammonia slip and ammonia emissions. The SCR test program included determining NO<sub>x</sub> removal efficiency, SO<sub>2</sub> to SO<sub>3</sub> oxidation rate, and ammonia slip. Preliminary analytical results for SO<sub>2</sub>, SO<sub>3</sub>, and ammonia were performed on-site by CleanAir personnel.

## Petrochemical Refinery; Morris, Illinois

Project Manager and Test Leader for multiple test programs on polyethylene and polypropylene production processes and waste gas flares at a petrochemical facility. The test programs included determining concentrations and mass emission rates of THC's and specific VOC's. VOC sampling programs included both collecting integrated grab samples in Tedlar bags or impingers for analysis by gas chromatography (GC) with multiple detectors, as well as direct interface sampling with GC/FID.

Test programs ranged from two-day test programs with two crew members to week-long, round the clock test programs with large test crews at multiple sources. Most test programs included on-site sample analysis using GC/FID.

## Coal-Fired Power Plant (SCR, DSI, and AH); Fruitland, NM

Project Manager and Test Leader for a performance test program conducted on dry sorbent injection (DSI), SCR, and tri-sector air pre-heater (APH) systems installed on a coal-fired boiler. The DSI and SCR testing included the determination of SO<sub>2</sub> to SO<sub>3</sub> conversion rate, NO<sub>x</sub> removal efficiency, NO<sub>x</sub> to ammonia distribution, ammonia slip, boundary to boundary and intermediate pressure drops, power consumption, sound pressure levels of system components, hydrated urea and hydrated lime consumption, and particulate emissions from material handling duct collectors.

Tri-sector APH testing included determining primary and secondary air draft losses and flue gas draft loss. The air to gas leakage across the APH, as well as outlet temperature (without leakage), were also determined.

The test program was conducted in a single mobilization using a 15man test crew over an 11-day period. Preliminary analytical results for SO<sub>2</sub>, SO<sub>3</sub>, HCl, FPM, and ammonia were performed on-site by CleanAir personnel.

## Combined Cycle Gas Turbine; Bundang, South Korea

Project Manager for an emissions test program conducted on a combined cycle gas turbine generator to collect data for completing construction permits for future similar installations in the United States. Pollutant emissions determined included FPM and CPM, NO<sub>x</sub>, CO, THC, methane, ethane, propane, propylene, iso-butane, butane and butene. Preparation and mobilization for the project, including the shipment of all test equipment and reagents, were conducted in a period of less than two weeks.

## Professional Certifications & Qualifications

OSHA 10-Hour

Hazardous Materials Shipping Certification

NSC CPR/AED Certification

NSC First-Aid Certification

Qualified Source Testing Individual (QSTI) Test Exams (Certificate No. 2008-271):

- Group 1 (Manual Gas Volume and Flow Measurements and Isokinetic Particulate Sampling Methods) – exam passed on 03/10/2017 (certification attached)
- Group 2 (Manual Gaseous Pollutants Source Sampling Methods) – exam passed on 06/01/2017 (certification attached)
- Group 3 (Gaseous Pollutants Source Sampling Methods) – exam passed on 06/01/2017 (certification attached)
- Group 4 (Hazardous Metals Measurement Methods) – exam passed on 07/09/2015 (certification attached)

Qualified Individual (QI)

Field Test Leader	Field Laboratory	Project Manager
Performance Specification 11 (PS11 – Particulate Matter)	SW-846 Test Method 0011 (Aldehydes & Ketones)	SW-846 Test Method 0030/0031 (Volatile Organic Compounds)
Performance Specification 12B (PS12B – Mercury Using Sorbent Trap)	EPA Method 22 (Fugitive Emissions)	EPA Methods 23 / SW-846 0010/0023A (PCDD/PCDF/SVOC)
EPA Method 25 (Total Gaseous Non-Methane Organics)	Trace Metals	EPA Method 204 (Permanent or Temporary Total Enclosure)
SW-846 Test Method 0061 / EPA Method 306 (Chromium)	Conditional Test Method 027 (Ammonia)	Other Test Method 29 (Hydrogen Cyanide)
Modified EPA Conditional Test Method 013 Controlled Condensation Method	CARB Method 501 (Size Distribution of Particulate Matter)	

## Education

Southern Illinois University; Carbondale, Illinois

Bachelor of Science in Mechanical Engineering Technology, 1988

William Rainey Harper College; Palatine, Illinois

Associate of Arts in Liberal Arts, 1985

# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT


**WILLIAM F. ANSELL, Jr.**


HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR


### **MANUAL GAS VOLUME MEASUREMENTS AND ISOKINETIC PARTICULATE SAMPLING METHODS**


ISSUED THIS 10<sup>TH</sup> DAY OF MARCH 2017 AND EFFECTIVE UNTIL MARCH 9<sup>TH</sup>, 2022





  
Peter R. Westlin, QSTI/QSTO Review Board

  
Peter S. Pakalnis, QSTI/QSTO Review Board

  
Theresa Lowe, QSTI/QSTO Review Board

  
J. Wade Bice, QSTI/QSTO Review Board

  
Karen D. Kajjya-Mills, QSTI/QSTO Review Board

  
Bruce Randall, QSTI/QSTO Review Board

CERTIFICATE  
NO.  
2008-271



# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT

**WILLIAM F. ANSELL, Jr.**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

### **MANUAL GASEOUS POLLUTANTS SOURCE SAMPLING METHODS**

ISSUED THIS 1<sup>ST</sup> DAY OF JUNE 2017 AND EFFECTIVE UNTIL MAY 30<sup>TH</sup>, 2022

Peter R. Westlin, QSTI/QSTO Review Board

Peter S. Pakalnis, QSTI/QSTO Review Board

Theresa Lowe, QSTI/QSTO Review Board

J. Wade Bice, QSTI/QSTO Review Board

Karen D. Kajiya-Mills, QSTI/QSTO Review Board

Bruce Randall, QSTI/QSTO Review Board



CERTIFICATE

NO.

2008-271

# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT

**WILLIAM F. ANSELL, Jr.**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

### **GASEOUS POLLUTANTS INSTRUMENTAL SAMPLING METHODS**

ISSUED THIS 1<sup>ST</sup> DAY OF JUNE 2017 AND EFFECTIVE UNTIL MAY 30<sup>TH</sup>, 2022



*Peter R. Westlin*

Peter R. Westlin, QSTI/QSTO Review Board

*A. Pakalnis*

Peter S. Pakalnis, QSTI/QSTO Review Board

*Theresa M. Lowe*

Theresa Lowe, QSTI/QSTO Review Board

*J. Wade Bice*

J. Wade Bice, QSTI/QSTO Review Board

*Karen D. Kajlya-Mills*

Karen D. Kajlya-Mills, QSTI/QSTO Review Board

*Bruce Randall*

Bruce Randall, QSTI/QSTO Review Board

CERTIFICATE

NO.

2008-271

# SOURCE EVALUATION SOCIETY



## Qualified Source Testing Individual

LET IT BE KNOWN THAT

**WILLIAM F. ANSELL, JR.**

HAS SUCCESSFULLY PASSED A COMPREHENSIVE EXAMINATION AND SATISFIED EXPERIENCE REQUIREMENTS IN ACCORDANCE WITH THE GUIDELINES ISSUED BY THE SES QUALIFIED SOURCE TEST INDIVIDUAL REVIEW BOARD FOR

### **HAZARDOUS METALS MEASUREMENT SAMPLING METHODS**

ISSUED THIS 9<sup>TH</sup> DAY OF JULY 2015 AND EFFECTIVE UNTIL JULY 8<sup>TH</sup>, 2020

A handwritten signature in black ink, appearing to read 'Peter R. Westlin'.

Peter R. Westlin, QSTI/QSTO Review Board

A handwritten signature in black ink, appearing to read 'Peter S. Pakalnis'.

Peter S. Pakalnis, QSTI/QSTO Review Board

A handwritten signature in black ink, appearing to read 'Theresa M. Lowe'.

Theresa Lowe, QSTI/QSTO Review Board

A handwritten signature in black ink, appearing to read 'C. David Bagweff'.

C. David Bagweff, QSTI/QSTO Review Board

A handwritten signature in black ink, appearing to read 'Karen D. Kajiya-Mills'.

Karen D. Kajiya-Mills, QSTI/QSTO Review Board

A handwritten signature in black ink, appearing to read 'Glenn C. England'.

Glenn C. England, QSTI/QSTO Review Board



CERTIFICATE  
NO.

2008-271

**This Page Intentionally Left Blank**